

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

Ness County. Sec. 9 Twp. 20 Rge. 21 (E) W (W)

Location as "NE/CNW%SW%" or footage from lines C SE NE

Lease Owner Quality Supply Company, Inc.

Lease Name Beltz Well No. 1

Office Address Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole)

Date well completed 19

Application for plugging filed 19

Application for plugging approved 19


Plugging commenced 10-10-66 19

Plugging completed 10-13-66 19

Reason for abandonment of well or producing formation Depleted.

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Leo Massey

Producing formation Depth to top Bottom Total Depth of Well 4411 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	511'	None
				4-1/2"	4387'	2697'
RECEIVED STATE CORPORATION COMMISSION						
OCT 19 1966						

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed from feet to feet for each plug set.

Checked hole, pumped plug to bottom and dumped 3 sacks of cement with dump bailer. Pulled 4 1/2" casing, and pumped in 15 sacks of gel mud and 125 sacks of cement into 8-5/8" casing to cap well.

PLUGGING COMPLETE.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor KNIGHT CASING PULLING COMPANY

Address CHASE, KANSAS

STATE OF KANSAS, COUNTY OF RICE, ss.

Noel J. Knight (employee of owner) or (Notary Public)

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel J. Knight

Chase, Kansas

(Address)

SUBSCRIBED AND SWORN TO before me this 15th day of October, 1966

Milton J. Volin

Notary Public.

My commission expires May 20, 1968

ROTARY DRILLING LOG

COMPANY: Pickrell Drilling Company
705 4th National Bank Bldg.
Wichita, Kansas

Rotary Drilling Commenced 10--5-64

Rotary Drilling Completed 10-16-64

LOCATION: Beltz No. 1, C SE NE Section 9-20-21W, Ness County, Kansas

CONTRACTOR: **PICKRELL DRILLING COMPANY**
Wichita, Kansas

CASING RECORD: 511' (24 jts) 8 5/8" surface casing set with 280 sacks cement.
Circulated. 135 jts 4 1/2" casing set at 4387 1/2' with 100 sacks
cement. Completed at 12:45 A.M. October 16, 1964

LOG

(Figures indicate bottom of formation — measurements from top of rotary bushing.)

RECEIVED
STATE CORPORATION COMMISSION


SEP 22 1966

60	Top Soil & Clay	<u>C. F. S.</u>
159	Clay & Shale	4325
512	Shale & Shells	4336
630	Shale	4380
805	Red Beds	4385
820	Blaine	4390
905	Red Beds & Shale	
1150	Sandy	
1470	Shale & Shells	
1505	Anhydrite	<u>Slope Test</u>
1870	Shale & Shells	1500
2325	Shale, Shells & Lime	2500
2445	Lime & Shale	3500
2730	Lime	4000
3880	Lime & Shale	
4175	Lime	
4245	Lime & Shale	<u>S. L. M.</u>
4315	Lime	2375
4385	Lime & Shale	3235
4390	Mississippian - RTD	4160

The undersigned, C. W. SEBITS, Attorney-in-Fact for PICKRELL DRILLING COMPANY, hereby certifies, in behalf of said Company, that the above is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Reports.

PICKRELL DRILLING COMPANY

By [Signature]
C. W. Sebitts Attorney-in-Fact



} ss.:

On this 22nd day of October, 19 64, before me the undersigned, a Notary Public, in and for

the County and State aforesaid, personally appeared C. W. Sebitts, to me known to be the identical person who subscribed the name of PICKRELL DRILLING COMPANY to the foregoing instrument as its Attorney-in-Fact and acknowledged to me that he executed the same as his free and voluntary act and deed, and as the free and voluntary act and deed of such company, for the uses and purposes therein set forth.

Given under my hand and seal of office the day and year last above written.

My commission expires: June 21, 1966

[Signature]
Maxine Blackman Notary Public