


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
P. O. Box 17027
Wichita, Kansas 67217
NORTH

WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

Ness County. Sec. 9 Twp. 20S Rge. 21W (E) (W)
Location as "NE/CNW%SW%" or footage from lines 250' NW of C SE NE
Lease Owner Palomino Petroleum
Lease Name Beltz Well No. #1
Office Address 500 Insurance Building, Wichita, Kansas 67202
Character of Well (completed as Oil, Gas or Dry Hole) dry hole
Date well completed November 25, 1979 19
Application for plugging filed November 25, 1979 19
Application for plugging approved November 25, 1979 19
Plugging commenced November 25, 1979 19
Plugging completed November 25, 1979 19
Reason for abandonment of well or producing formation dry hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Marion Schmidt
Producing formation Depth to top Bottom Total Depth of Well 4419' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Hole plugged with 50-50 pozmix, 6% gel, as follows: 70 sacks @ 120',
20 sacks @ 390', hulls and 10 sacks @ 40', 2 sacks in mousehole,
3 sacks in rathole. Plugging completed at 11:45 p.m., November 25, 1979.

12-12-79


(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Strata Drilling Company
Address P. O. Box 355, Great Bend, Kansas 67530

STATE OF KANSAS COUNTY OF BARTON ss.
Charles W. Steincamp (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Charles W. Steincamp
P. O. Box 355, Great Bend, Kansas 67530 (Address)

Subscribed and sworn to before me this 3rd day of December, 1979



Loneita Barry
Notary Public.

D R I L L E R S L O G

#1 Beltz

CASING RECORD: 10 jts. new 20# 8-5/8" surface casing	COMPANY: Palomino Petroleum	DESCRIPTION: 250' NW C SE NE Section 9-20S-21W Ness County, Kansas
	CONTRACTOR: Strata Drilling Company	
	COMMENCED: November 19, 1979	
TOTAL ROTARY DEPTH: 4419'	COMPLETED: November 25, 1979	ELEVATION:

D & A

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Post rock, shale and shells	0	415	Ran 402' new 20# 8-5.8" surface casing; set and cemented @ 407' with 230 sacks common, 2% gel, 3% C.C. Cement circulated. Plug down at 1:00 a.m., November 20, 1979.
Shale, sand, shale	415	1460	
Anhydrite	1460	1500	
Shale	1500	1905	
Shale and lime	1905	4419	
			Ran one drill stem test.
			Hole plugged with 50-50 pozmix, 6% gel, as follows: 70 sacks @ 720', 20 sacks @ 390', hulls and 10 sacks @ 40'; 2 sacks in mousehole, 3 Sacks in rathole. Plugging completed at 11:45 p.m., November 25, 1979.

STATE OF KANSAS)
)ss
COUNTY OF BARTON)

I certify that this is a true and correct copy of the above log to the best of my knowledge.

STRATA DRILLING COMPANY

Charles W. Steincamp
Charles W. Steincamp

Sworn to and subscribed before me this 3rd day of December, 1979.

My appointment expires: 3-28-80.

Loneita Barry
Loneita Barry, Notary Public

