


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
P. O. Box 17027
Wichita, Kansas 67217
NORTH

WELL PLUGGING RECORD



Locate well correctly on above Section Plat

Pawnee County, Sec. 26 Twp. 20S Rge. 20W (E) (W)
Location as "NE/CNW/SE/SW" or footage from lines. SW NE
Lease Owner Mr. Glen N. Rupe
Lease Name Tombaugh Well No. 1
Office Address 925 Olive Garvey Building, Wichita, Kansas 67202
Character of Well (completed as Oil, Gas or Dry Hole) D & A
Date well completed November 9 19 73
Application for plugging filed November 9 19 73
Application for plugging approved November 9 19 73
Plugging commenced November 9 19 73
Plugging completed November 9 19 73
Reason for abandonment of well or producing formation D & A

If a producing well is abandoned, date of last production 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Leo F. Massey
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4,298 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	262'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plug @ 500' w/50 sx.
Plug @ 240' w/25 sx.
Plug @ 40' w/1 sk. hulls & 10 sx cement.
Used Common Cmt. w/2% Gel.

RECEIVED
STATE CORPORATION COMMISSION
NOV 21 1973
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Red Tiger Drilling Company
Address 1720 Wichita Plaza, Wichita, Kansas 67202

STATE OF Kansas COUNTY OF Sedgwick, ss.
Linda H. Dickens (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Linda H. Dickens
1720 Wichita Plaza, Wichita, Kansas 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 19th day of November, 19 73

My commission expires May 24, 1977
LINDA C. MOWREY
NOTARY PUBLIC
SEDGWICK CO. KANS.

Linda C. Mowrey
Notary Public.

DRILLERS LOG

No. 1 Tombaugh

CASING RECORD:	COMPANY: Mr. Glen N. Rupe	DESCRIPTION:
8-5/8" @ 262' w/175 sx cement	CONTRACTOR: Red Tiger Drilling Co.	SW NE 26-20S-20W Pawnee County, Kansas
TOTAL DEPTH: 4,298'	COMMENCED: October 31, 1973	COMPLETED: November 9, 1973

ELEVATION:

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Post Rock	0	40	
Sand & Shale	40	263	
Shale & Shells	263	740	
Sand	740	930	
Shale & Shells	930	1290	
Anhydrite	1290	1327	
Shale & Shells	1327	1750	
Shale & Lime	1750	2360	
Lime	2360	2455	
Lime & Shale	2455	2920	
Lime	2920	3100	
Lime & Shale	3100	3300	
Lime w/Shale Streaks	3300	3470	
Lime & Shale	3470	3920	
Lime	3920	4180	
Lime & Chert	4180	4250	
Lime	4250	4298	Chert @ 4,298'

RECEIVED
STATE CORPORATION COMMISSION
NOV 21 1973
CONSERVATION DIVISION
Wichita, Kansas

I certify that this is a true and correct copy of the above log to the best of my knowledge.

RED TIGER DRILLING COMPANY

Linda H. Dickens
Linda H. Dickens

Subscribed and sworn to before me this 19th day of November, 1973.

Linda C. Murray
Notary Public

My Commission Expires:

