


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kans.

WELL PLUGGING RECORD

Pawnee County. Sec. 25 Twp. 20 Rge. 20 (E) W (W)

Location as "NE/CNW/SW" or footage from lines NW NW SE
Lease Owner Honaker-Davis Drlg. Co.
Lease Name Haas Well No. 1
Office Address 2008 Lakin, Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 11-30 1956
Application for plugging filed 11-30 1956
Application for plugging approved 11-30 1956
Plugging commenced 10:30 A.M. 11-30 1956
Plugging completed 12:30 P.M. 11-30 1956
Reason for abandonment of well or producing formation _____



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Russell Brundee
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4326 Feet
Show depth and thickness of all water, oil and gas formations.


OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	443	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy rotary mud to 425'. Put in 1/3 sack hulls. Set plug then dumped in 25 sacks cement.
Filled hole with heavy rotary mud to 35 feet. Put in 1/3 sack hulls. Set plug. Dumped in 10 sacks of cement.
Cement filled hole to bottom of cellar.



(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor _____
Address _____

STATE OF Kansas, COUNTY OF Barton, ss.
S. C. Lingreen (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God?

(Signature) S. C. Lingreen
Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 3rd day of December 1956

Kenneth G. Fischer
Kenneth G. Fischer, Notary Public.

My commission expires 6-25-59

PLUGGING
FILE SEC. 25 T. 20 R. 20W
BOOK PAGE 122 L. E. 1

DRILLERS LOG

No. 1
Loc: NW 1/4 SE
Sec: 25-20S-20W
Pawnee County, Kansas
Company: Monaker-Davis Drig. Co., et al
Contractor: Monaker-Davis Drig. Co.

Coms: 11-18-56
Comp: 11-30-56
Rotary Total Depth: 4326'
Casing: 8-5/8" at 443'
D & A

0	70	Top soil & Post rock	
70	155	Clay, Blue Shale & sand	
155	650	Shale & Sand	
650	1345	Shale & Red Bed	8-5/8" casing cemented at
1345	1375	Anhydrite	443' with 250 sacks cement
1375	2050	Shale & Red Bed	and 6 sacks calcium chloride
2050	3825	Lime & Shale	
3825	3880	Lime	
3880	4326	Lime & Shale	
4326		Rotary Total Depth	D & A

I certify that this is the true and correct copy of the above log to the best of my knowledge.

Joe J. Monaker

Joe J. Monaker

Subscribed and sworn to before me this 4th day of December, 1956.

Kenneth G. Fischer

Kenneth G. Fischer, Notary Public

My commission expires: 6-25-59

PLUGGING
FILE SEC. 25 T. 20 R. 20W
BOOK PAGE 122 LINE 1

RECEIVED
STATE CORPORATION COMMISSION
DECEMBER 1956
MORTGAGE DIVISION
WICHITA, KANSAS