


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

Pawnee County, Sec. 24 Twp. 20 Rge. (E) 20 (W)

Location as "NE/CNW%SW%" or footage from lines SE SW SE
Lease Owner Musgrove Petroleum Corporation
Lease Name STURGEON Well No. 1
Office Address 801 Union Center, Wichita, Kansas.
Character of Well (completed as Oil, Gas or Dry Hole) Dry hole
Date well completed November 26, 1956
Application for plugging filed verbally - November 25, 1956
Application for plugging approved verbally - November 25, 1956
Plugging commenced November 26, 1956
Plugging completed November 26, 1956
Reason for abandonment of well or producing formation Dry



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? verbally - yes.

Name of Conservation Agent who supervised plugging of this well _____
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4344 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	422'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy mud to 390'.
1st Plug set at 390' w/20 sx cement.
Filled hole with heavy mud to 35'.
2nd Plug set at 35' w/10 sx cement.

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Musgrove Petroleum Corporation
Address 801 Union Center, Wichita, Kansas.

STATE OF Kansas, COUNTY OF Sedgwick, ss.
I, Gordon L. Koelling (employee of owner) or (owner/operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Gordon L. Koelling
801 Union Center, Wichita, Kansas.
(Address)

SUBSCRIBED AND SWORN TO before me this 28th day of November, 1956

My commission expires June 16, 1959.

RECEIVED
STATE CORPORATION COMMISSION
11-29-56

Notary Public.

PLUGGING 20W
FILE SEC. 24 T. 20 R. CONSERVATION DIVISION
BOOK PAGE 120 LINE 9
Wichita, Kansas
NOV 29 1956

CONTRACTOR'S WELL LOG

COMPANY: Musgrove Petroleum Corporation
 CONTRACTOR: Musgrove Petroleum Corporation
 FARM: STURGEON #1
 LOCATION: SE SW SE Sec. 24-20S-20W
 Pawnee County, Kansas
 COMMENCED: November 11, 1956
 COMPLETED: November 26, 1956

0	90	Surface soil, sand & rock
90	275	Clay, shale & sand
275	422	Shale, shells & clay
422	565	Shale
565	620	Red bed & shale
620	800	Shale & shells
800	1000	Sand
1000	1366	Shells & shale
1366	1400	Anhydrite
1400	2000	Shale & shells
2000	2245	Shale
2245	3745	Shale & lime
3745	4277	Lime
4277	4290	Lime & sand
4290	4315	Sand & shale
4315	4342	Shale & lime
4342	4344	Lime
	4344	Rotary Total Depth

Set 8-5/8" surface casing at 422' with 275 sacks cement, 2% calcium chloride.
 DRY AND ABANDONED

ELEVATION:	2230' K. B.	Base K. C.	4087' (-1857)
SAMPLE TOPS:		Cherokee Shale	4224' (-1994)
Heebner	3700' (-1470)	Cherokee Sand	4278' (-2048)
Lansing	3750' (-1520)	Mississippi	4318' (-2088)

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

I, Gordon L. Koelling, do hereby certify that the above and foregoing is a true and correct copy of the log of the STURGEON #1, SE SW SE, Section 24-20S-20W, Pawnee County, Kansas, as reflected by the files of the Musgrove Petroleum Corporation

MUSGROVE PETROLEUM CORPORATION
 BY Gordon L. Koelling
 Secretary-Treasurer

Subscribed and sworn to before me, a Notary Public, in and for Sedgwick County, Kansas, this 28th day of November, 1956.

Leah Joyce Hays
 Notary Public

My commission expires June 16, 1959.

RECEIVED
 STATE DEPARTMENT OF REVENUE
 PLUGGING
 SEC 24 T 20 R 20W
 BOOK PAGE 120 LINE 9