


WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

Pawnee County, Sec. 2 Twp. 20S Rge. (E)20 (W)

NORTH



Locate well correctly on above  
Section Plat

Location as "NE/CNW%SW%" or footage from lines C NW NE  
Lease Owner Abercrombie Drilling, Inc.  
Lease Name FRICK Well No. 1  
Office Address 801 Union Center, Wichita, Kansas 67202  
Character of Well (completed as Oil, Gas or Dry Hole) Dry  
Date well completed May 8, 19 64  
Application for plugging filed verbally May 7, 19 64  
Application for plugging approved verbally May 8, 19 64  
Plugging commenced May 8, 19 64  
Plugging completed May 8, 19 64  
Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? verbally yes - written May 12, 1964

Name of Conservation Agent who supervised plugging of this well Eldon Petty  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4480 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	459'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Set 1st plug at 450' w/20 sx cement  
Set 2nd plug at 180' w/20 sx cement  
Set 3rd plug at 40' w/ cement to surface.  
Cement cap on rat hole.

RECEIVED  
STATE CORPORATION COMMISSION

MAY 18 1964  
5-18-64

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Abercrombie Drilling, Inc.  
Address 801 Union Center, Wichita, Kansas 67202


STATE OF Kansas, COUNTY OF Sedgwick, ss.  
B. Lynn Herrington (employee of owner) or (~~owner or operator~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) B. Lynn Herrington  
801 Union Center, Wichita, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 14th day of May, 19 64

Leah Faye Hefke  
Leah Faye Hefke Notary Public.

My commission expires June 16, 1967



CONTRACTOR'S WELL LOG

COMPANY: Abercrombie Drilling, Inc.  
 CONTRACTOR: Abercrombie Drilling, Inc.  
 FARM: FRICK #1  
 LOCATION: C NW NE  
 Section 2-20S-20W  
 Pawnee County, Kansas  
 COMMENCED: April 22, 1964  
 COMPLETED: May 8, 1964

0	305	Surface Clay & Shale
305	620	Shale
620	825	Red Bed
825	1035	Sand
1035	1125	Shale & Sand
1125	1425	Shale
1425	2215	Shale & Shells
2215	3495	Shale & Lime
3495	3593	Lime
3593	3795	Lime & Shale
3795	4212	Lime
4212	4270	Lime & Shale
4270	4334	Lime
4334	4417	Lime & Chert
4417	4462	Chert
4462	4480	Lime
	4480	Rotary Total Depth

Set 8-5/8" surface casing at 459' with 300 sx common cement

DRY & ABANDONED

ELECTRIC LOG TOPS:		ELEVATION:	2255' G. L.
			2261' D. F. & K. B.
Heebner	3737' (-1476)		
Toronto	3757' (-1496)		
Lansing/Kansas City	3784' (-1523)		
Base Kansas City	4111' (-1850)		
Cherokee	4242' (-1981)		
Mississippian	4346' (-2085)		
Kinderhook	4449' (-2188)		

**RECEIVED**  
 STATE CORPORATION COMMISSION

MAY 18 1964

STATE OF KANSAS )  
 ) SS  
 COUNTY OF SEDGWICK )

CONSERVATION DIVISION  
 Wichita, Kansas

I, B. Lynn Herrington, do hereby certify that the above and foregoing is a true and correct copy of the log of the FRICK #1, C NW NE, Section 2-20S-20W, Pawnee County, Kansas, as reflected by the files of Abercrombie Drilling, Inc.

B. Lynn Herrington  
 B. Lynn Herrington

Subscribed and sworn to before me, a Notary Public, in and for Sedgwick County, Kansas, this 14th day of May, 1964.

Leah Faye Hefke  
 Leah Faye Hefke, Notary Public

My commission expires June 16, 1967.