

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
301 S. Market, Room 2078  
Wichita, KS 67202

WELL-PLUGGING RECORD

RECEIVED  
K.A.C. 02-5-117

NOV 13 2001

KCC WICHITA

NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

API NUMBER 15-145-21,437.0000

LEASE NAME Seltman

WELL NUMBER 1

660 Ft. from N Section Line

330 Ft. from E Section Line

SEC. 2 TWP. 20S RGE. 20W (E) or (W)

COUNTY Pawnee

Date Well Completed \_\_\_\_\_

Plugging Commenced 10-3-01

Plugging Completed 10-8-01

LEASE OPERATOR Palomino Petroleum, Inc.

ADDRESS 4924 SE 84th St. Newton, Kansas 67114-8827

PHONE#(316) 799-1000 OPERATORS LICENSE NO. 30742

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on \_\_\_\_\_ (date)

by Richard Lacey (KCC District Agent's Name).

Is ACO-1 filed? \_\_\_\_\_ If not, is well log attached? \_\_\_\_\_

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. 4330'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	538.30	None
				5-1/2"	4328	2430'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugging material is used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each side. Plugged off bottom with sand to 4160' and 5 sacks cement. Shot pipe @2600' and 2430'. Pulled up to 1450', pumped 50 sks. cement and 10 sks. gel, pulled up to 550', pumped 50 sks. cement, pulled up to 40' and pumped 10 sks. cement to surface. 60/40 pos. 6% gel.

Plugging Complete.

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529

Address P.O. Box 467 Chase, Kansas 67524

Name of Party Responsible for Plugging Fees: Palomino Petroleum, Inc.

State of Kansas County of Rice, ss.

Mike Kelso (Employee of Operator) or (Operator)

of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and circumstances stated herein, and that the statements, and matters herein contained and the log of the above-described well as filed therewith, are true and correct, so help me God.

(Signature) [Signature]

(Address) P. O. Box 467 Chase, KS 67524

SUBSCRIBED AND SWORN TO before me this 24th day of October ~~XX~~ 2001

[Signature]  
Notary Public

My Commission Expires: \_\_\_\_\_

NOTARY PUBLIC - State of Kansas  
IRENE HERZBERG  
My Appt. Exp. 8-24-01