


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Pawnee County, Sec. 36 Twp. 20 Rge. 19 (E8) (W)

Location as "NE/CNW/SW" or footage from lines NE NE NE

Lease Owner Musgrove Petroleum Corporation

Lease Name A.F. Brann - Union National Bank Bldg Well No. 1

Office Address 518 Petroleum Building

Character of Well (completed as Oil, Gas or Dry Hole) Dry hole

Date well completed June 14, 19 53

Application for plugging filed June 22, 19 53

Application for plugging approved 19

Plugging commenced June 14, 19 53

Plugging completed June 14, 19 53

Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Unknown

Producing formation Depth to top Bottom Total Depth of Well 4158 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	156'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Loaded hole with mud at 255'.
Set first plug with 20 sacks of cement.
Second plug with 10 sacks of cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Musgrove Petroleum Corporation

Address 518 Petroleum Building, Wichita, Kansas

STATE OF Kansas, COUNTY OF County, ss.

Gordon L. Koelling (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.


(Signature) Gordon L. Koelling

518 Petroleum Building, Wichita, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 22nd day of June, 19 53

Mary L. Sumner Notary Public.

My commission expires Nov. 14, 1956



CONTRACTOR'S WELL LOG

COMPANY: A.F. Brann
 CONTRACTOR: Musgrove Petroleum Corporation
 FARM: Fox # 1
 LOCATION: NE NE NE Section 36-20-19
 Pawnee County, Kansas
 COMMENCED: May 27, 1953
 COMPLETED: June 14, 1953

0	120	Shale
120	130	Shale and red bed
130	156	Shale and shells
156	515	Shale, sand and shells
515	645	Shells and red bed
645	795	Dakota sand and shells
795	930	Shale and shells
930	1010	Red bed
1010	1223	Shale
1223	1245	Anhydrite
1245	1485	Shale and shells
1485	2400	Lime and shale
2400	2465	Lime
2465	2530	Lime and shale
2530	2635	Shale, lime and shells
2635	3135	Lime and shale
3135	3215	Shale and shells
3215	4024	Shale and lime
4024	4030	Sand
4030	4042	Cherty Conglomerate
4042	4057	Conglomerate and sand
4057	4140	Conglomerate and chert
4140	4158	Cherty cong. and Arbuckle
	4158	Rotary Total Depth

Set 8 5/8" surface casing at 156' with 110 sacks of cement.

Dry and abandoned.

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

I, GORDON L. KOELLING, do hereby certify that the above and foregoing is a true and correct copy of the log of the Fox # 1 NE NE NE of Section 36-20-19, in Pawnee County, Kansas, as reflected by the files of the Musgrove Petroleum Corporation.

RECEIVED
 STATE CORPORATION COMMISSION
 JUN 24 1953
 CONSERVATION DIVISION
 Wichita, Kansas

MUSGROVE PETROLEUM CORPORATION
 By *Gordon L. Koelling*
 Secretary-Treasurer

Subscribed and sworn to before me a Notary Public in and for Sedgwick County, Kansas, this 22nd of June, 1953.

Mary L. Sumner
 Notary Public

My Commission Expires: Nov. 14, 1956

PLUGGING
 FILE SEP 36 7 20 P 1960
 BOOK PAGE 107 LINE 44