

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas

Position \_\_\_\_\_ County. Sec. 36 Twp. 20 Rge. 19 (E) \_\_\_\_\_ (W) \_\_\_\_\_

Location as "NE/CNW/SW" or footage from lines NE 1/4 Sec 36 Twp 20 Rge 19

Lease Owner J. A. Allison

Lease Name Flow R Well No. 1

Office Address 1415 Wichita Plaza Wichita, Kansas 67202

Character of Well (completed as Oil, Gas or Dry Hole) \_\_\_\_\_

Date well completed \_\_\_\_\_ 19 \_\_\_\_\_

Application for plugging filed 4-7-1971

Application for plugging approved 4-7-1971


Plugging commenced 4-12-1971

Plugging completed 4-17-1971

Reason for abandonment of well or producing formation \_\_\_\_\_

If a producing well is abandoned, date of last production \_\_\_\_\_ 19 \_\_\_\_\_

Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES



Name of Conservation Agent who supervised plugging of this well Leo Massey  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4095 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8"	368	0
				5 1/2"	4094	3060

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Push plug to 3850 - send back to 3825 - dump 5 sac cement.  
Pull 2060 ft. 5 1/2" pipe.  
Globe Cementing Co. pumped 5 sac bulis - 20 sac gel & 120 sac cement to surface.

RECEIVED  
STATE CORPORATION COMMISSION  
MAY 19 1971  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Ralph Comstock Pipe Pulling, Inc. # 490  
Address Stafford, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.  
J. A. ALLISON (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J. A. Allison  
1415 Vickers-KSB&T Bldg., Wichita, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 18th day of May, 1971

My commission expires January 14, 1974  
Frances O. Erhard  
Frances O. Erhard Notary Public.

B & B DRILLING, INC.  
207 Petroleum Building  
Wichita, Kansas 67202

April 28, 1970

RECEIVED  
STATE CORPORATION COMMISSION  
APR 8 1971  
CONSERVATION DIVISION  
Wichita, Kansas

DRILLERS LOG

Re: Fox "B" #1  
NW NE NE Section 36-208-19W  
Pawnee County, Kansas

OPERATOR: J. A. Allison  
CONTRACTOR: B & B Drilling, Inc.  
COMMENCED: April 16, 1970  
COMPLETED: April 26, 1970  
TOTAL DEPTH: 4095'

Set 8 5/8" casing @ 368' w/ 180 sx

0	40	Surface Clay
40	369	Surface Clay
369	1254	Shale & Sand
1254	1280	Anhydrite
1280	1590	Shale & Lime
1590	2270	Shale & Lime
2270	2737	Lime & Shale
2737	3307	Lime & Shale
3307	3508	Lime & Shale
3508	3992	Lime
3992	4077	Lime
4062	4095	Coring to total depth
4095		Total Depth Set 5 1/2" @ 4094 w/100 sx

We certify the above and foregoing to be true and correct copy of the log on the # 1 Fox "B", located in Pawnee County, Kansas.

Gill Lohar President

Alma A. Newser Notary Public  
Subscribed and sworn to before me this  
28th day of April, 1970.

My commission expires May 31, 1970