


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bittling Building  
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above  
Section Plat

Pawnee County. Sec. 34 Twp. 20 Rge. (E) 19 (W)  
Location as "NE/CNW%SW%" or footage from lines SE SE NW  
Lease Owner Musgrove Petroleum Corporation  
Lease Name Geo. E. Johnson Well No. 1-A  
Office Address 518 Petroleum Building, Wichita, Kansas.  
Character of Well (completed as Oil, Gas or Dry Hole) Dry hole  
Date well completed October 23, 1954  
Application for plugging filed verbally October 22, 1954  
Application for plugging approved verbally October 23, 1954  
Plugging commenced October 23, 1954  
Plugging completed October 23, 1954  
Reason for abandonment of well or producing formation Dry hole

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? verbally - yes

Name of Conservation Agent who supervised plugging of this well M. A. Rives  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4530 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	338'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled hole with mud to 350'.  
Set 1st plug at 350' with 20 sx cement.  
Filled hole with mud to 35'.  
Set 2nd plug at 35' with 10 sx cement & 1/2 sack hulls.

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Musgrove Petroleum Corporation  
Address 518 Petroleum Building, Wichita, Kansas.

STATE OF Kansas, COUNTY OF Sedgwick  
I, Gordon L. Koelling, (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Gordon L. Koelling  
518 Petroleum Building, Wichita, Kans.  
(Address)

SUBSCRIBED AND SWORN TO before me this 26th day of October, 1954

My commission expires September 24, 1956.

Thomas L. Steimans  
Notary Public.

PLUGGING  
FILED SEC 34 T 20 R 19W  
BOOK PAGE 72 LINE 29

10-28-54

CONTRACTOR'S WELL LOG

COMPANY:	Musgrove Petroleum Corporation
CONTRACTOR:	Musgrove Petroleum Corporation
FARM:	Geo. E. Johnson #1-A
LOCATION:	SE SE NW, Sec. 34-20-19 Pawnee County, Kansas.
COMMENCED:	October 10, 1954
COMPLETED:	October 23, 1954

0	15	Clay
15	90	Post rock
90	150	Post rock & shale
150	300	Shale
300	615	Blue shale
615	810	Red bed
810	970	Sand
970	1035	Red bed
1035	1380	Shale & shells
1380	1410	Anhydrite
1416	2090	Shale & shells
2090	2250	Shale & lime streaks
2250	3813	Shale & lime
3813	3930	Lime
3930	3965	Shale & lime
3965	4202	Lime
4202	4370	Lime & shale
4370	4380	Lime, shale & chert
4380	4431	Lime & shale
4431	4465	Lime, chert & shale
4465	4479	Lime & chert
4479	4530	Lime, chert & shale
	4530	Rotary Total Depth

Set 8-5/8" surface pipe at 338' with 200 sacks of cement, 2% calcium chloride.

Dry and Abandoned.

STATE OF KANSAS )  
                          ) SS  
COUNTY OF SEDGWICK )

I, Gordon L. Koelling, do hereby certify that the above and foregoing is a true and correct copy of the log of the George E. Johnson #1-A, SE SE NW of Section 34-20-19, Pawnee County, Kansas, as reflected by the files of the Musgrove Petroleum Corporation.

MUSGROVE PETROLEUM CORPORATION

BY Gordon L. Koelling  
Secretary-Treasurer

Subscribed and sworn to before me, a Notary Public, in and for Sedgwick County, Kansas, this 26th day of October, 1954.

William R. Stinson  
Notary Public

My commission expires September 24, 1956.

PLUGGING  
PLI sec 34-20-19  
BOOK PAGE 28 LINE 29