


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

Pawnee County, Sec. 34 Twp. 20 Rge. (E) 19 (W)

NORTH



Locate well correctly on above
Section Plat

Location as "NE/CNW%SW%" or footage from lines SE SE NW
Lease Owner Musgrove Petroleum Corporation
Lease Name GEO. E. JOHNSON Well No. 1
Office Address 518 Petroleum Building, Wichita, Ks.
Character of Well (completed as Oil, Gas or Dry Hole) Lost the hole
Date well completed October 9, 19 54
Application for plugging filed verbally - October 8, 19 54
Application for plugging approved verbally - October 8, 19 54
Plugging commenced October 9, 19 54
Plugging completed October 9, 19 54
Reason for abandonment of well or producing formation Lost the hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? verbally yes. Written 10-11-54

Name of Conservation Agent who supervised plugging of this well Warren H. Horner, Box 207, Great Bend
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3296 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	382'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with mud to 380'.
Set 1st plug at 380' w/ 1/3 sack hulls & 25 sx cement.
Filled hole with mud to 35'.
Set 2nd plug at 35' w/ 10 sx cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Musgrove Petroleum Corporation
Address 518 Petroleum Building, Wichita, Kansas.

STATE OF Kansas, COUNTY OF Sedgwick, ss.
I, Gordon L. Koelling (employee of owner) or (~~owner/operator~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Gordon L. Koelling
518 Petroleum Building, Wichita, Kansas.
(Address)

SUBSCRIBED AND SWORN TO before me this 12th day of October, 19 54

My commission expires September 24, 1956.

Theresa L. Stenmark
Notary Public

PLUGGING
FILE SEC 34 T 20 R 19W
BOOK PAGE 69 LINE 45

FILE
STATE CORPORATION
OCT 13 1954
CONSERVATION DIVISION
WICHITA, KANSAS

CONTRACTOR'S WELL LOG

COMPANY: Musgrove Petroleum Corporation
 CONTRACTOR: Musgrove Petroleum Corporation
 FARM: Geo. E. Johnson #1
 LOCATION: SE SE NW, Sec. 34-20-19
 Pawnee County, Kansas.
 COMMENCED: September 30, 1954
 COMPLETED: October 9, 1954

0	10	Surface clay
10	80	Post rock
80	160	Shale & post rock
160	270	Shale
270	285	Red bed
285	610	Blue shale
610	850	Red bed
850	940	Sand
940	1270	Red bed & shale
1270	1477	Shale & lime
1477	1820	Shale & salt
1820	1950	Shale & shells
1950	2200	Shale & lime streaks
2200	3296	Shale & lime
	3296	Rotary Total Depth

Set 8-5/8" surface pipe at 382' with 200 sacks cement & 3 sx calcium chloride.
 Lost the hole.

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

I, GORDON L. KOELLING, do hereby certify that the above and foregoing is a true and correct copy of the log of the JOHNSON #1, SE SE NW, Section 34-20-19, Pawnee County, Kansas, as reflected by the files of the Musgrove Petroleum Corporation.

MUSGROVE PETROLEUM CORPORATION

By Gordon L. Koelling
 Secretary-Treasurer

Subscribed and sworn to before me, a Notary Public, in and for Sedgwick County, Kansas, this 12th day of October, 1954.

Miss R. Stumpe
 Notary Public

My commission expires September 24, 1956.

PLUGGING
 REC. SEC. 34-20-19
 BOOK PAGE 49 LINE 45

STATE OF KANSAS
 DIVISION
 RECEIVED