

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

Form CP-4
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Pawnee SEC. 32 TWP. 20S RGE. 19W E/W
Location as in quarters or footage from lines:
C SE SE

Locate Well
correctly on above
Section Platt.

Lease Owner L.D. Davis
Lease Name Freeland #1 Well No. _____
Office Address Rt. 1 Box 183-B Great Bend, Kansas 67530
Character of Well (Completed as Oil, Gas or Dry Hole): _____
Date Well Completed _____
Application for plugging filed _____
Plugging commenced 8-7-82
Plugging completed 8-12-82
Reason for abandonment of well or producing formation Depleted

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Steve Durrant

Producing formation _____ Depth to top _____ bottom T.D. 4330'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8-5/8"	358'	none
				4-1/2"	4329'	2320'

Describe in detail the manner in which the well was plugged, indicating where the mud
fluid was placed and the method or methods used in introducing it into the hold. If cement
or other plugs were used, state the character of same and depth placed, from _____ feet
to _____ feet for each plug set.

Pumped bottom with 35 sacks 50/50 pos, pushed bottom plug to 3910'. Shot casing @3339', 3044', 2903', 2786', 2673', 2424' and 2321'. Pulled a total of 70 joints of 4-1/2" casing. Plugged well with 3 sacks hulls, 15 sacks gel, 70 sacks cement, 1 sack hulls, 10 sacks gel, 8-5/8" plug, 80 sacks cement.

Plugging Complete.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Kelso Casing Pulling

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (employee of owner) or (owner or operator) of the
above-described well, being first duly sworn on oath, says: That I have knowledge of the
facts, statements, and matters herein contained and the log of the above-described well as
filed and that the same are true and correct. So help me God.

RECEIVED
STATE CORPORATION COMMISSION

AUG 19 1982 8-19-82

(Signature) R. Darrell Kelso
Box 347 Chase, Ks. 67524
(Address)

SUBSCRIBED AND SWORN TO before me this 18th day of August, 19 82



My Commission expires:


Irene Hoover
Notary Public.

KANSAS GEOLOGICAL SURVEY

500 S. WICHITA, KANSAS

K.G.S. LIBRARY

AUG 12 1971



ROTARY DRILLING LOG

32-20-19W
CSE SE
Elev. 2145' KB
Dry/Min

Operator: George Reed
FREELAND #1
C SE SE Section 32-20S-19W
Pawnee County, Kansas

Contractor: Rains & Williamson
Oil Co., Inc.

Commenced: 6-29-71
Completed: 7-6-71

Casing: 8-5/8"/358'/200 sacks

Formations

Surface Clay	70'
Sand and Shale	170'
Shale	720'
Sand	880'
Shale and Red Bed	1305'
Anhydrite	1329'
Shale	1560'
Shale and Lime	2090'
Lime and Shale	3595'
Lime	4285'
Rotary Total Depth	4285'
	4330'

Log Jap

Stone Coral 1308
Heelover 3660
Lansing 3714
BK 3992
Ft Scott 4167
cher 4182
Miss 4270

DST (1) 4272.85

We certify the above log is true and correct, to the best of our knowledge and belief.

RAINS & WILLIAMSON OIL CO., INC.

"OWWO"

L.D. Davis #1 Freeland
IP: P 8 BOPD + 40 BOPD Miss 4272-74
Card Issued: 6/16/76


NEW INFO: Re-entered 5/6/76; Wsh dwn to
4330, Set 4 1/2" 4329/200, MICT - PF 4272
-74, Swb 2 1/2 BPPH, Nat, Pop, P 8 BOPD Wilson Rains
+ 40 BOPD

Wilson Rains

Subscribed and sworn to before me, a Notary Public within and for the State of Kansas, County of Sedgwick, this 8 day of July, 1971.

Jeanine Durand
Jeanine Durand Notary Public

My Commission Expires: 3-31-74



RECEIVED
STATE CORPORATION COMMISSION
AUG 02 1982
CONSERVATION DIVISION
Wichita, Kansas