

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-055-20774-00-00
Spot: SW Sec/Twnshp/Rge: 21-22S-32W
1345 feet from S Section Line, 3922 feet from E Section Line
Lease Name: HETT B Well #: 2-21
County: FINNEY Total Vertical Depth: 2810 feet

Operator License No.: 32864
Op Name: XTO ENERGY INC.
Address: 210 PARK AVE STE 2350
OKLAHOMA CITY, OK 73102

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		2551		WITH 2 SX CMT
PROD	5.5	2810	0	WITH 285 SX CMT
SURF	8.625	320		WITH 275 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 11/28/2017 10:00 AM
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.
Proposal Rcvd. from: MONTY CATHCART Company: XTO ENERGY Phone: (620) 482-1565

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 11/29/2017 11:00 AM KCC Agent: KEN JEHLIK

Actual Plugging Report:

11/28/17: CIBP @ 2551' WITH 2 SX CMT. PUMP 100 SX CMT FROM 2114' TO 1200'. RUN CBL FROM 1200' TO 220'. TOP OF GOOD CMT AT 650' WITH CMT STRINGERS UP TO 294'. PERFORATE 4 HOLES AT 267'. 11/29/17: RUN TBG TO 1135'. SPOT 80 SX CMT UP TO 300'. TOOH WITH TBG, CIRCULATE CMT TO SURFACE THROUGH PERFS AT 267' WITH 120 SX CMT LEAVING THE CASING & ANNULUS FULL OF CMT. TOP OFF WITH 5 SX CMT.

Perfs:

Top	Bot	Thru	Comments
2698	2708		
2640	2674		
2610	2620		

INVOICED
JAN 11 2018

Remarks: USED CLASS C COMMON CEMENT BY ORR ENTERPRISES.

Plugged through: TBG

District: 01

12-8-17
RECEIVED
DEC - 8 2017
KCC DODGE CITY

Signed _____

[Signature]
SA

(TECHNICIAN)