

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-055-00257-00-00  
Spot: NENESENW Sec/Twnshp/Rge: 28-22S-32W  
3900 feet from S Section Line, 2887 feet from E Section Line  
Lease Name: HETT B Well #: 1-28  
County: FINNEY Total Vertical Depth: 2750 feet

Operator License No.: 32864  
Op Name: XTO ENERGY INC.  
Address: 210 PARK AVE STE 2350  
OKLAHOMA CITY, OK 73102

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		2614		WITH 5 SX CMT
PROD	5.5	2749	0	WITH 350 SX CMT
SURF	8.625	437		WITH 350 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/30/2017 1:00 PM  
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.  
Proposal Rcvd. from: MONTY CATHCART Company: XTO ENERGY Phone: (620) 482-1565

Proposed Plugging Method: Set a CIBP @ 2611' to isolate Chase perfs, circ hole w/ mud and cap w/ 5 sks Class C cement. Spot 100 sks Class C cement from 2100' to 800' to cover BTW @ 1150'. Perf squeeze holes @ 450'. Establish circulation to surface on 8 5/8" x 5 1/2" annulus. Squeeze w/ 150 sks of cement & circulate to surface. Cut & cap well. Weld on ID plate.

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 12/01/2017 3:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

\*\*SQUEEZED CASING LEAK @ 1273' WITH 100 SX CMT\*\* CIBP @ 2614' WITH 5 SX CMT. PUMP 100 SX CMT FROM 2110' TO 1200'. FULL CIRCULATION. RUN CBL FROM 1200' TO 400'. TOC @ 650'. PERFORATE 4 HOLES AT 455'. RUN TBG TO 1136' & SPOT 65 SX CMT UP TO 500'. TOOH WITH TBG & CIRCULATE CMT TO SURFACE THROUGH PERFS AT 455" USING 150 SX CMT LEAVING THE 5 1/2" CASING & 5 1/2" X 8 5/8" ANNULUS FULL OF CMT.

Perfs:


Top	Bot	Thru	Comments
2724	2734		
2692	2702		
2661	2688		

Remarks: USED CLASS C COMMON CEMENT BY ORR ENTERPRISES.

Plugged through: TBG

District: 01

Signed



(TECHNICIAN)

12-7-17  
RECEIVED  
DEC - 7 2017  
KCC DODGE CITY