

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-109-20028-00-01
Spot: E2W2SESW Sec/Twnshp/Rge: 10-11S-32W
660 feet from S Section Line, 3453 feet from E Section Line
Lease Name: OAKLEY UNIT Well #: 3-4
County: LOGAN Total Vertical Depth: 4697 feet

Operator License No.: 30606
Op Name: MURFIN DRILLING CO., INC.
Address: 250 N WATER STE 300
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	4693		285 SX
SURF	8.625	261		200 SX

Well Type: EOR UIC Docket No: E24979.2 Date/Time to Plug: 12/01/2017 9:00 AM
Plug Co. License No.: 34059 Plug Co. Name: HURRICANE SERVICES, INC.
Proposal Rcvd. from: JOHN TURNER Company: MURFIN DRILLING CO., INC. Phone: (785) 443-1031

Proposed Plugging Method: Ordered 450 sx 60/40 pozmix 4% gel cement, 800 # gel and 1000# hulls.
8 5/8" surface casing set at 261' w/200 sx cement.
5 1/2" production casing set at 4693' w/285 sx cement.
Perforated at 1845' w/270 sx cement.
150 sx cement top down. TOC at 85' and base at 700'.
TD 4697', PBTD 4656'.
Perforations: 4209'-4213', 4240'-4242', 4263'-4266', 4283'-4291', 4298'-4306', 4323'-4327', 4366'-4370', 4589'-4594', 4590'-4592', 4596'-4598', 4603'-4618', 4605'-4609'.
Junk in hole. Top of fish at 3735'.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 12/01/2017 12:15 PM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

Perfs:

Perforated production casing at 2589'. Ran tubing to 3665' and pumped 120 sx cement w/250 # hulls. 50 sx cement pumped without hulls. Pulled tubing to 3326' and pumped 800 # gel. Pulled tubing to 2587' and pumped 125 sx cement w/300 # hulls. Pulled tubing to 1293' and pumped 150 sx cement w/200 # hulls. Cement circulated to surface. Pulled tubing to surface. Connected to 5 1/2" production casing and pumped 25 sx cement. Connected to 8 5/8" surface casing and pumped 25 sx cement. Pressured to 300 psi.

GPS: 39.10656N -100.86115W

INVOICED
JAN 10 2018

Remarks: HURRICANE SERVICES PULLING UNIT AND CEMENT SERVICE TICKET # 10,850.

Plugged through: TBG

District: 04

Received Signed
KANSAS CORPORATION COMMISSION

Darrel Dipman
(TECHNICIAN)

CM

DEC 20 2017

DEC 01 2017

CONSERVATION DIVISION
WICHITA, KS

Form CP-2/3