

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-033-10031-00-01  
Spot: SWSWNENW Sec/Twnshp/Rge: 6-31S-16W  
3984 feet from S Section Line, 3833 feet from E Section Line  
Lease Name: ROBBINS Well #: 1 SWD  
County: COMANCHE Total Vertical Depth: 4923 feet

Operator License No.: 8061  
Op Name: OIL PRODUCERS, INC. OF KANSAS  
Address: 1710 WATERFRONT PKWY  
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4475		WITH 2 SX CMT
PROD	4.5	4921	1007	WITH 175 SX CMT
SURF	8.625	503		WITH 300 SX CMT

Well Type: SWD UIC Docket No: D28050.0 Date/Time to Plug: 12/11/2017 9:30 AM  
Plug Co. License No.: 34059 Plug Co. Name: HURRICANE SERVICES, INC.  
Proposal Rcvd. from: JORDAN DISKIN Company: OIL PRODUCERS Phone: (316) 681-0231

Proposed Plugging Method: SET CIBP @ 4475' WITH 2 SX CMT. PLUG AT 850' WITH 10 SX GEL & 50 SX CMT. PLUG AT 535' WITH 50 SX CMT. PLUG AT 60' WITH 20 SX CMT.

Plugging Proposal Received By: SCOTT ALBERG WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 12/11/2017 11:55 AM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

BOTTOM PERFS WERE SQUEEZED WTH 50 SX CMT. SET CIBP @ 4475' WITH 2 SX CMT. 1ST PLUG AT 858' WITH 10 SX GEL & 50 SX CMT WITH 100# HULLS. 2ND PLUG AT 548' WITH 50 SX CMT. 3RD PLUG AT 60' WITH 20 SX CMT. CMT CIRCULATED.

Perfs:

Top	Bot	Thru	Comments
4841	4865		
4512	4570		

INVOICED  
JAN 10 2018


Remarks: \*\*COMPLIANCE ISSUE: FAILED MIT\*\* USED 60/40 POZMIX 4% GEL BY HURRICANE SERVICES.

Plugged through: TBG

District: 01

12-12-17  
RECEIVED  
DEC 12 2017  
KCC DODGE CITY

Signed

  
(TECHNICIAN)