

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-151-20254-00-01
Spot: NWNWSESE Sec/Twnshp/Rge: 24-29S-14W
1051 feet from S Section Line, 1046 feet from E Section Line
Lease Name: ANDREWS UNIT Well #: 2
County: PRATT Total Vertical Depth: 3905 feet

Operator License No.: 3911
Op Name: RAMA OPERATING CO., INC.
Address: 101 S MAIN ST
STAFFORD, KS 67578

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		1980		WITH 2 SX CMT
CIBP		2969		
PROD	5.5	3905	830	WITH 350 SX CMT
SURF	8.625	255		WITH 250 SX CMT

Well Type: SWD UIC Docket No: D27622.0 Date/Time to Plug: 12/05/2017 8:30 AM
Plug Co. License No.: 7868 Plug Co. Name: KIZZAR WELL SERVICING, INC.
Proposal Rcvd. from: RANDY GNIEST Company: RAMA OPERATING Phone: (620) 234-5191

Proposed Plugging Method: SET CIBP @ 2100' WITH 2 SX CMT. PLUG AT 800' WITH 10 SX GEL & 50 SX CMT. PLUG AT 280' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: STEVE PFEIFER WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 12/05/2017 11:00 AM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

SET CIBP @ 1980' & PUT 2 SX CMT ON TOP OF CIBP THROUGH DUMP BAILER.
PRESSURE TEST CASING TO 200#. HELD. 1ST PLUG AT 790' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 280' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 30 SX CMT.

Perfs:

Top	Bot	Thru	Comments
2168	2173		

INVOICED
JAN 10 2018

Remarks: **COMPLIANCE ISSUE: NOV MIT LTR SENT** USED 60/40 POZMIX 4% GEL BY BASIC.

Plugged through: CSG

District: 01

12-8-17

RECEIVED
DEC - 8 2017

KCC DODGE CITY

Signed Stephen J. Pfeifer
(TECHNICIAN)

588