

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-053-00484-00-01  
Spot: NESWNE5W Sec/Twnshp/Rge: 18-17S-9W  
1675 feet from S Section Line, 3342 feet from E Section Line  
Lease Name: WILKENS Well #: 4  
County: ELLSWORTH Total Vertical Depth: 3394 feet

Operator License No.: 3911  
Op Name: RAMA OPERATING CO., INC.  
Address: 101 S MAIN ST  
STAFFORD, KS 67578

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP	4.5	2600		
PROD	4.5	2855	1350	100 SX
SURF	8.25	217		100 SX

Well Type: SWD UIC Docket No: D20080.0 Date/Time to Plug: 12/12/2017 9:00 AM  
Plug Co. License No.: 7868 Plug Co. Name: KIZZAR WELL SERVICING, INC.  
Proposal Rcvd. from: ROBIN AUSTIN Company: RAMA OPERATING CO. Phone: (620) 234-5191

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: JEFF KLOCK Witness Type: NONE  
Date/Time Plugging Completed: 12/12/2017 1:00 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

MIRU, PULL OUT TUBING AND PACKER. \*OPERATOR DID NOT GET AN ARBUCKLE BOTTOM PLUG PUT IN WELL. SET CIBP AT 2600' AND CAP WITH 2 SX'S CEMENT. SHOOT 4.5" CASING OFF AT 1350'. RUN TUBING IN TO 1250' AND PUMP 35 SX'S COMMON WITH 3% CC. PULLED TUBING TO 900' AND WAIT 1 HOUR. TAGGED CEMENT AT 1100'. PUMPED 35 SX'S COMMON WITH 3% CC AT 900' WITH GOOD CIRCULATION, PULLED TUBING TO 265' AND CIRCUALTED 60-40 POZ 4% GEL TO SURFACE. PULLED TUBING OUT AND TOPPED OFF.

Perfs:

Top	Bot	Thru	Comments
2855	3394	OH	

INVOICED  
JAN 10 2018

Remarks: BASIC SERVICES #16252 FAILED MIT.

Plugged through: TBG

District: 02

Signed Virgil Clothier  
(TECHNICIAN)