

TO:

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-163-20436-00-01

Spot: SWSENENE Sec/Twnshp/Rge: 34-8S-18W

4235 feet from S Section Line, 387 feet from E Section Line

Lease Name: HARRIS

Well #: 1 SWD

County: ROOKS

Total Vertical Depth: 1424 feet

Operator License No.: 34179

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	1424		325 SX
SURF	8.625	196		130 SX

Op Name: THOMAS M. BROWN LLC

Address: PO BOX 250
PLAINVILLE, KS 67663

Well Type: SWD

UIC Docket No: D18414.0

Date/Time to Plug: 12/07/2017 8:30 AM

Plug Co. License No.: 99977

Plug Co. Name: QUALITY OIL WELL CEMENTING

Proposal Rcvd. from: JAKE BROWN

Company: THOMAS M. BROWN LLC DBA

Phone: (785) 737-7070

Proposed: 4 1/2' casing cemented to surface with 325 sx cement.

Plugging: Cedar Hills perforations: 1010' - 1100'.

Method:

Ordered 200 sx 60/40 pozmix 4% gel cement w/700 # hulls.

Plugging Proposal Received By: RICHARD WILLIAMS

WitnessType: COMPLETE (100%)

Date/Time Plugging Completed: 12/07/2017 10:00 AM

KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Quality Oilwell Cementing pumped 150 sx cement w/600 # hulls mixed in. Maximum pressure 500 psi. Shut in pressure 400 psi. Hooked up to backside with instant pressure to 300 psi.

Perfs:

Top	Bot	Thru	Comments
1046	1100		

INVOICED
JAN 11 2018

Remarks: QUALITY OIL WELL CEMENTING TICKET # 562

Plugged through: CSG

District: 04

Signed Richard Williams

(TECHNICIAN)

CM

Received
KANSAS CORPORATION COMMISSION

DEC 20 2017

CONSERVATION DIVISION
WICHITA, KS

DEC 11 2017

Form CP-2/3