

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-077-21758-00-00
Spot: E2NENENE Sec/Twnshp/Rge: 35-34S-5W
330 feet from N Section Line, 200 feet from E Section Line
Lease Name: SHEEN Well #: 1-35
County: HARPER Total Vertical Depth: 5336 feet

Operator License No.: 34621
Op Name: RENDA ENERGY LLC
Address: 2525 MCKINNEY AVE., STE B
DALLAS, TX 75201

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	5329		340 SX
SURF	8.625	350		
T1	2.875	4908		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/26/2013 12:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: RENDA ENERGY, LLC Company: _____ Phone: (214) 731-9208

Proposed Plugging Method: PER KCC RULES AND REGULATIONS.

Plugging Proposal Received By: STEVE BOND Witness Type: PARTIAL
Date/Time Plugging Completed: 09/27/2013 12:00 AM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

9/14/2013. RIG MOVED IN. RIGGED UP FOR RODS AND LAID OUT 100 7/8" SINGLES. 9/15/2013 LAID OUT 94 RODS. RIGGED OVER. LAID OUT 152 JOINTS OF 2 7/8" TUBING. TORE RIG DOWN AND MOVED OFF. 9/26/2013 SET RIG IN. SET BP @ 4640' AND DUMPED 5 SX CEMENT WITH BAILER. DUG OUT CELLAR AND PIT. SET CASING JACKS IN. PULLED STRETCH, 30". CUT CASING @ 3300'. SHUT DOWN. 9/27/2013 PULLED 5 1/2" CASING TO 950'. RIGGED UP, COPELAND CEMENT PUMPED 35 SX 60/40 POZ 6% GEL. PULLED UP TO 450', CIRCULATED CEMENT TO SURFACE WITH 200 SX 60/40 POZ 6% GEL. PULLED REST OF CASING. PLUGGING COMPLETE.

Perfs:

Top	Bot	Thru	Comments
4850	4870		
4828	4844		
4816	4820		
4790	4802		
4778	4784		
4737	4760		
4718	4737		
4714	4760		
4680	4700		

FOR IMAGING ONLY-PLUG DATE EXCEEDS 5 YEAR BILLING CUTOFF

Remarks: COPELAND CEMENT

Plugged through: CSG

District: 02

Signed _____


(TECHNICIAN)

JK