

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-135-20461-00-00  
Spot: NESW Sec/Twnshp/Rge: 8-20S-21W  
1920 feet from S Section Line, 1920 feet from W Section Line  
Lease/Unit Name: YOUNT Well Number: 1  
County: NESS Total Vertical Depth: 4436 feet

Operator License No.: 5316  
Op Name: FALCON EXPLORATION, INC.  
Address: 155 N. MARKET, STE. 1020  
WICHITA, KS 67202

Production Casing Size: 5.5 feet: 4426 WITH 100 SX CMT  
Surface Casing Size: 8.625 feet: 376 WITH 200 SX CMT

#144<sup>17</sup>

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 08/22/2003 11:30 AM  
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.  
Proposal Rcvd. from: LEON KUHN Company: FALCON EXPLORATION Phone: (785) 483-1559

Proposed Plugging Method: SAND TO 4300' & 4 SX CMT. PRESSURE TEST CASING TO 500#. PERFORATE & PUMP CMT. PRESSURE TEST. CHECK BACKSIDE.

Plugging Proposal Received By: MICHAEL MAIER WitnessType: Plugging Operations 100% Witnessed (Complete)  
Date/Time Plugging Completed: 08/22/2003 4:15 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:  
OPEN HOLE. 1ST PLUG SANDED TO 4300' & 4 SX CMT. 2ND PLUG TEST CASING TO 500#. PERFORATE AT 725' & PUMPED 140 SX CMT. DID NOT CIRCULATE. MAXIMUM PRESSURE 500#. SHUT IN WITH 150#. 3RD PLUG PUMPED 150 SX CMT DOWN 8 5/8" ANNULUS. MAXIMUM PRESSURE 500#. SHUT IN WITH 250#.

RECEIVED  
SEP 04 2003  
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY SWIFT SERVICES. NO CASING RECOVERED.  
Plugged through: CSG

District: 01  
RECEIVED  
AUG 25 2003  
KCC Dodge City

Signed Michael Maier  
(TECHNICIAN)  
INVOICED  
DATE 9.5.03  
INV. NO. 2004060476

Form CP-27