

To: 1 090523 2-28
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 135-21,625 .0000

SE NE NW, SEC. 18, T 20 S, R 21 W/EX

4290 feet from S section line

2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5086

Lease Name Maier Well # 1

Operator: Pintail Petroleum, Ltd.

County Ness

Name & Address 225 N. Market, Ste. 300

Well Total Depth 4380 142.35 feet

Wichita, KS 67202

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 428

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor D S & W Well Servicing, Inc. License Number 6901

Address P.O. Box 231, Claflin, KS 67525

Company to plug at: Hour: 10 a.m. Day: 28 Month: 2 Year: 19 95

Plugging proposal received from Kevin Strube

(company name) D S & W Well Servicing, Inc. (phone) 316-587-3361

were: 5 1/2" at 4368' w/175 sx cement, Open hole 4368-80'

1st plug sand back to 4300' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 5 sx gel and 60 sx cement at 615',

3rd plug pull to 450' and spot 50 sx cement,

4th plug pull to 40' and spot 10 sx cement.

RECEIVED
STATE CORPORATION COMMISSION
3-2-95
MAR 1 2 1995
CONSERVATION DIVISION
WICHITA, KANSAS

Plugging Proposal Received by Steve Middleton
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 11:20 a.m. Day: 28 Month: 2 Year: 19 95

ACTUAL PLUGGING REPORT 1st plug sanded back to 4300' and dumped 5 sx cement on top of sand through bailer,

2nd plug pumped 5 sx gel and 60 sx cement at 615',

3rd plug pulled to 450' and spotted 50 sx cement,

4th plug pulled to 40' and spotted 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 615' of 5 1/2" casing.
(if additional description is necessary, use BACK of this form)

INVOICED
(If additional description is necessary, use BACK of this form) observe this plugging.

DATE 3-9-95

Signed [Signature]
(TECHNICIAN)

INV. NO. 42235