

To: 1 090146
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

11-29

183

API NUMBER 15- 135-23,624.0000
150' S & 106' W of
C S/2 NW, SEC. 10, T 20 S, R 21 W/4

TECHNICIAN'S PLUGGING REPORT

Operator License # 6009
Operator: Double Eagle Exploration, Inc.
Name & Address: 800 W. 47th, Suite 318
Kansas City, MO 64112

3150 feet from S section line
4066 feet from E section line
Lease Name J.&L. Kramer Well # 1
County Ness 143.97
Well Total Depth 4430 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 389

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Duke Drilling Company, Inc. License Number 5929
Address 310 W. Central, Wichita, KS 67202

Company to plug at: Hour: 4:30 p.m. Day: 29 Month: 11 Year: 19 91

Plugging proposal received from Jay Snider
(company name) Duke Drilling Company, Inc. (phone) 316-267-1331

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1464-93'

1st plug at 1500' with 50 sx cement, 2nd plug at 900' with 80 sx cement,

3rd plug at 550' with 50 sx cement, 4th plug at 400' with 50 sx cement.

5th plug at 40' with 10 sx cement,

6th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Steve Middleton (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 6 p.m. Day: 29 Month: 11 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug at 1500' with 50 sx cement,

2nd plug at 900' with 80 sx cement,

3rd plug at 550' with 50 sx cement,

4th plug at 400' with 50 sx cement,

5th plug at 40' with 10 sx cement,

6th plug to circulate rathole with 15 sx cement.

RECEIVED
STATE CORPORATION COMMISSION
DEC 03 1991
CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel 1/4# Flosbal by Allied.
(if additional description is necessary, use BACK of this form.)

INVOICED
I (could / did not) observe this plugging.

DATE 12-9-91

Signed [Signature] (TECHNICIAN)

INV. NO. 34047
11-29 JAN 28 1992

USE:

EFFECTIVE DATE: 11-23-91

State of Kansas

NOTICE OF INTENTION TO DRILL 135-23,624

Must be approved by the K.C.C. five (5) days prior to commencing well

Expected Spud Date November 19, 1991

Spot 150'S & 106'W of East
C. S/2. NW. Sec. 10. Twp. 20. S. Rg. 21. X West

OPERATOR: License # 6009
Name: DOUBLE EAGLE EXPLORATION, INC.
Address: 800 W. 47th - Suite 318
City/State/Zip: Kansas City, Missouri 64112
Contact Person: Jim Thompson
Phone: 316/269-0400

3150 feet from South / ~~line~~ line of Section
4066 feet from East / ~~line~~ line of Section
IS SECTION X REGULAR IRREGULAR?

(NOTE: Locate well on the Section Plat on Reverse Side)

CONTRACTOR: License # 5929
Name: DUKE DRILLING CO., INC.

County: Ness
Lease Name: J. & L. Kramer Well #: 1
Field Name: Betz

Well Drilled For: Well Class: Type Equipment:
X. Oil ... Enh Rec .X Infield .X Mud Rotary
... Gas ... Storage ... Pool Ext. ... Air Rotary
... OUVG ... Disposal ... Wildcat ... Cable
... Seismic: ... # of Holes ... Other
... Other

Is this a Prorated/Spaced Field? .X. yes ... no
Target Formation(s): MISSISSIPPI

Nearest lease or unit boundary: 1214'
Ground Surface Elevation: 2236' feet MSL

Water well within one-quarter mile: ... yes .X. no
Public water supply well within one mile: ... yes .X. no

Depth to bottom of fresh water: 100'
Depth to bottom of usable water: 900'

Surface Pipe by Alternate: 1 .X. 2
Length of Surface Pipe Planned to be set: 350'

Length of Conductor pipe required: N/A
Projected Total Depth: 4450'

Formation at Total Depth: Miss
Water Source for Drilling Operations:

if OUVG: old well information as follows:
Operator:
Well Name:
Comp. Date: Old Total Depth

... well ... farm pond .X. other
DWR Permit #:

Directional, Deviated or Horizontal wellbore? ... yes .X. no

Will Cores Be Taken? ... yes .X. no

If yes, true vertical depth:
Bottom Hole Location:

If yes, proposed zone:

200' Alt. II Req.

Exp. 5/18/92

AFFIDAVIT

The undersigned hereby affirms that the drilling, completion and eventual plugging of this well will comply with K.S.A. 55-101, et. seq.

624

Pusher Jay SPUD DATE 11-22-91 INIT. SM

LENGTH SURFACE PLANNED 300'

RESERVE PIT STATUS- REMOVE FLUID LINED
after salt sect. bbls. when done bbls.

RATHOLED AHEAD? Y N SIZE HOLE
SURFACE PIPE 8 5/8" @ 389 CONDUCTOR
ANHYDRITE T- 14621 B- 1493 ELEVATION

TD 1430 FORMATION MISS

RAN PIPE @ SX DV TOOL SX ALT II DONE Y N

Arbuckle Plug @ 50 Ft. W/ SX

Hug./Council @ 500 Ft. W/ SX

Anhydrite Base @ 900 Ft. W/ 50 SX

1/2 Base Anhy. @ 900 Ft. W/ 80 SX

1/2, 1/2 Plug @ 550 Ft. W/ 50 SX

Bottom Surface @ 400 Ft. W/ 50 SX

40' Plug @ 40 Ft. W/ 10 SX

RAT HOLE CIRC/W SX MOUSE HOLE W/ SX

WATER WELL SX (Irr. Well Pond ---)
Hauling ---

TECHNICIAN SM DATE 11-27-91

TYPE OF CEMENT 60/60 675 Portland

STARTING TIME 4:30 (AM/PM) DATE 11-29-91

COMPLETION TIME 6:30 (AM/PM) DATE 11-29-91

CEMENT COMPANY allied