

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-135-23937-00-00
Spot: SWNWNE Sec/Twnshp/Rge: 19-20S-21W
990 feet from N Section Line, 2160 feet from E Section Line
Lease/Unit Name: SCHABEN Well Number: 1
County: NESS Total Vertical Depth: 4397 feet

Operator License No.: 4058
Op Name: AMERICAN WARRIOR, INC.
Address: PO BOX 399
GARDEN CITY, KS 67846

Conductor Pipe: Size _____ feet:
Surface Casing: Size 8.625 feet: 250 WITH 155 SX CMT
Production: Size 5.5 feet: 4384 WITH 100 SX CMT
Liner: Size _____ feet: 142.90

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/01/2001 10:40 AM
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.
Proposal Rcvd. from: TED Company: SWIFT SERVICES, INC. Phone: (785) 798-2300

Proposed Plugging Method: PUMP 300# HULLS & 50 SX CMT TO BOTTOM. DISPLACE WITH GEL TO 1450' AND PUMP 145 SX CMT. TIE ONTO BACKSIDE AND PUMP 20 SX CMT.

Plugging Proposal Received By: MICHAEL MAIER WitnessType: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 08/01/2001 11:45 AM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

OPEN HOLE. DV TOOL @ 1426', CEMENT CIRCULATED TO SURFACE. PUMP 300# HULLS & 50 SX CMT TO BOTTOM. GEL DISPLACEMENT TO 1450' AND PUMPED 145 SX CMT. MAXIMUM PRESSURE 450#. SHUT IN 200#. TIED ONTO BACKSIDE AND PUMPED 20 SX CMT. PRESSURED TO 500# AND HELD.

Remarks: USED 60/40 POZMIX 6% GEL BY SWIFT SERVICES. NO CASING RECOVERED.

Plugged through: CSG

INVOICED
DATE 8-13-01
INV. NO. 2002060219

District: 01

Signed Michael Maier
(TECHNICIAN)

RECEIVED

AUG - 9 2001

KCC WICHITA

AUG 07 2001

Form CB-278

MP