

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-135-30239-00-00
Spot: CNWNE Sec/Twnshp/Rge: 19-20S-21W
660 feet from N Section Line, 1980 feet from E Section Line
Lease/Unit Name: JOHN WITTMAN, JR B Well Number: 1
County: NESS Total Vertical Depth: 4402 feet

Operator License No.: 4058
Op Name: AMERICAN WARRIOR, INC.
Address: PO BOX 399
GARDEN CITY, KS 67846

Conductor Pipe: Size _____ feet:
Surface Casing: Size 8.625 feet: 494 WITH 375 SX CMT
Production: Size 4.5 feet: 4387 WITH 150 SX CMT
Liner: Size _____ feet: \$143.07

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/06/2001 2:00 PM
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.
Proposal Rcvd. from: SCOTT CORSAIR Company: AMERICAN WARRIOR Phone: (785) 398-2270

Proposed Plugging Method: CIBP @ 3000'. 1ST PLUG AT 650' WITH 50 SX CMT. 2ND PLUG AT 510' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT. USE 15 SX GEL FOR SPACER.

Plugging Proposal Received By: STEVE MIDDLETON WitnessType: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 09/06/2001 4:30 PM KCC Agent: STEVE MIDDLETON

Actual Plugging Report:

BOTTOM SANDED IN. 1ST PLUG SHOT OFF 5 1/2" CASING AT 1520'. LAID DOWN 1 JOINT OF CASING AND PUMPED 15 SX GEL AND 30 SX CMT. 2ND PLUG PULLED CASING TO 700', PUMPED 40 SX CMT. 3RD PLUG PULLED CASING TO 525', PUMPED 50 SX CMT. 4TH PLUG PULLED CASING TO 40' AND CIRCULATED CEMENT TO SURFACE. GOOD CIRCULATION ON ALL PLUGS.

RECEIVED
9-10-01
SEP 10 2001
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY SWIFT SERVICES. RECOVERED 1520' OF 5 1/2" CASING.

Plugged through: CSG

District: 01

Signed _____

(TECHNICIAN)

SEP 07 2001

INVOICED

DATE 9-10-01

INV. NO. 2002060440

Form 02-2/3