

1050275

15.135.30253.0000

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- Completed 6-17-66
C SE NE, SEC. 26, T 20 S, R 21 W

TECHNICIAN'S PLUGGING REPORT

Operator License # 5310

_____ feet from N/S section line
_____ feet from W/E section line

Operator: Four-Way Operating, Inc.
Name & Address: Box 698
Great Bend, KS 67530

Lease Name Lewis Well # 1
County Ness
Well Total Depth 4361 ^{141.73} feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 345

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Rockhold Engineering, Inc. License Number 5111

Address Box 698, Great Bend, KS 67530

Company to plug at: Hour: 11:30 am Day: 2 Month: July Year: 19 84

Plugging proposal received from Deacon Pulley

(company name) Rockhold (phone) 316-792-2506

were: 5 1/2 at 4356' The well had been squeezed from 3730' to 300' with 1000 sx cement.
1st plug sand back to 4300' and dump 5 sx cement on top of sand through bailer
Pump 2 sx hulls, 7 sx gel and 200 sx cement.

Plugging Proposal Received by Richard W. Lacy
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 1:15 pm Day: 2 Month: July Year: 19 84

ACTUAL PLUGGING REPORT 5 1/2" set at 4356' The well had been squeezed from 3730' to 300'
with 1000 sx cement. 1st plug sanded back to 4300' & dumped 5 sx cement on top of sand.

Pumped 2 sx hulls, 7 sx gel and 200 sx cement.

Maximum pressure 1500 psi and shut in pressure 200 psi

RECEIVED
STATE CORPORATION COMMISSION
7-6-84
JUL 06 1984

Remarks: Used 60/40 Pozmix 2% gel 3% cc. They recovered 300' of 5 W/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 7-16-84

INV. NO. 2543

Signed Richard W. Lacy
(TECHNICIAN)