

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-135-24194-00-00
Spot: S2S2NE Sec/Twnshp/Rge: 26-20S-21W
2310 feet from N Section Line, 1320 feet from E Section Line
Lease/Unit Name: LEWIS Well Number: 1-26
County: NESS Total Vertical Depth: 4438 feet

Operator License No.: 5004
Op Name: VINCENT OIL CORPORATION
Address: 125 N. MARKET, STE 1075
WICHITA, KS 67202

Conductor Pipe: Size feet: 144.24
Surface Casing: Size 8.625 feet: 360
Production: Size feet:
Liner: Size feet:

Well Type: DH UIC Docket No: Date/Time to Plug: 09/09/2002 11:00 PM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Rcvd. from: ED MCKENNA Company: MURFIN DRILLING CO., INC. Phone: (316) 267-3241

Proposed Plugging Method: 1ST PLUG AT 1450' WITH 50 SX CMT. 2ND PLUG AT 700' WITH 50 SX CMT. 3RD PLUG AT 380' WITH 40 SX CMT. 4TH PLUG AT 40' WITH 10 SX CMT. 5TH PLUG TO CIRCULATE RAT HOLE WITH 15 SX CMT. NO MOUSE HOLE.

Plugging Proposal Received By: MICHAEL MAIER Witness Type: Plugging Operations Were Not Witnessed
Date/Time Plugging Completed: 09/10/2002 1:30 AM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

1ST PLUG AT 1450' WITH 50 SX CMT. 2ND PLUG AT 700' WITH 50 SX CMT. 3RD PLUG AT 380' WITH 40 SX CMT. 4TH PLUG AT 40' WITH 10 SX CMT. 5TH PLUG TO CIRCULATE RAT HOLE WITH 15 SX CMT. NO MOUSE HOLE.

RECEIVED
KANSAS CORP COMM
2002 SEP 30 A 11:49
9-30-02

Remarks: USED 60/40 POZMIX 6% GEL 1/4# FLO SEAL BY ALLIED.

Plugged through: DP

District: 01

Signed Michael Maier
(TECHNICIAN)

INVOICED

SEP 24 2002

DATE 10-1-02

INV. NO. 2003060601

Form CP 2/3