

1 070272

DEC 2 2 1986

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 135-21,571.0000  
SW SW SW, SEC. 10, T 20 S, R 23 W/R  
330 feet from S section line  
4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5181  
Operator: Donald C. Slawson  
Name & Address 200 Douglas Building  
Wichita, KS 67202

Lease Name McCreight "A" Well # 1  
County Ness 145.70  
Well Total Depth 4483 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 505

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050  
Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 1:15 p.m. Day: 22 Month: 12 Year: 1986

Plugging proposal received from Ron Hoover

(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2457

were: 4 1/2" at 4482' PBTD 4432' Perfs at 4395-97' Elevation 2268' GL

1st plug sand back to 4345' and dump 4 sx cement on top of sand through bailer,  
2nd plug squeeze well with 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls,  
release 8 5/8" wiper plug and pump 150 sx cement.

Plugging Proposal Received by Richard Lacey  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 2:15 p.m. Day: 22 Month: 12 Year: 1986

ACTUAL PLUGGING REPORT 1st plug sanded back to 4345' and dump 4 sx cement on top of sand  
through bailer.

2nd plug squeeze well with 300 lbs. hulls, 15 sx gel, 50. sx cement, 10 sx gel, 100 lbs.  
hulls, release 8 5/8" wiper plug and pump 150 sx cement.

Maximum pressure 700 psi and shut in 400 psi.

Remarks: Recovered 2800' of 4 1/2" casing. Used 60/40 Pozmix 6% gel by Allied.  
(If additional description is necessary, use BACK of this form.)

*Rec'd*  
**JAN 0 2 1987**

**INVOICED**  
(Copy of this report to observe this plugging.)

Signed Dan Goodwin  
(TECHNICIAN)

DATE 1-5-87  
INV. NO. 15765