

8-28-87

To: 1 030843
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 135-23,155-0000

TECHNICIAN'S PLUGGING REPORT

Operator License # 5004

Operator: Vincent Oil Corporation
Name & Address: 125 North Market, Suite 1110
Wichita, KS 67202

App. SW NE SW, SEC. 10, T 20 S, R 23 W/EX
1545 feet from S section line

3810 feet from E section line

Lease Name McCreight "B" Well # 1

County Ness 143.81

Well Total Depth 4425 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 514

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor H-30 Drilling, Inc. License Number 5107

Address 251 North Water, Suite 10, Wichita, KS 67202

Company to plug at: Hour: 7 a.m. Day: 28 Month: 8 Year: 19 87

Plugging proposal received from Rick Davis

(company name) H-30 Drilling, Inc. (phone) 316-793-3687

were: to fill hole with heavy mud and spot cement through drill pipe Elevation 2269'
Anhydrite 1503'

1st plug at 1530' with 50 sx cement, 2nd plug at 850' with 50 sx cement,
3rd plug at 540' with 40 sx cement, 4th plug at 40-0' with 10 sx cement,
5th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 9:45 a.m. Day: 28 Month: 8 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug at 1530' with 50 sx cement,
2nd plug at 850' with 50 sx cement,
3rd plug at 540' with 40 sx cement,
4th plug at 40' with 10 sx cement,
5th plug to circulate rathole with 15 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

SEP 1 1987
9-1-87
CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used 60/40 Pozmix 4% gel by Allied.
(If additional description is necessary, use BACK of this form.)

INVOICED

(If any) did not observe this plugging.

DATE 9-3-87

Signed Steve Durrant (TECHNICIAN)

INV. NO. 18021

NOTICE OF INTENTION TO DRILL

(see rules on reverse side)

Expected Spud Date... 8 month 15 day 87 year

API Number 15-135-23,155 Approx.

OPERATOR: License # 5004 Name Vincent Oil Corporation Address 125 No. Market, Suite 1110 City/State/Zip Wichita, Kansas, 67202 Contact Person Julie Stout Phone 262-3573

SW NE SW Sec. 10 Twp. 20 S, Rg. 23 X West 1545 Ft. from South Line of Section 3810 Ft. from East Line of Section

CONTRACTOR: License # 5107 Name H-30 Drilling, Inc. City/State Wichita, Kansas 67202

Nearest lease or unit boundary line 1170 feet County Ness Lease Name McCreight B Well # 1

Well Drilled For: X Oil Storage Infield Mud Rotary Gas Inj Pool Ext Air Rotary OWWO Expl X Wildcat Cable

Ground surface elevation 2269 feet MSL Domestic well within 330 feet: yes X no Municipal well within one mile: yes X no

If OWWO: old well info as follows:

Depth to bottom of fresh water 320 Depth to bottom of usable water 380 480 Surface pipe by Alternate: 1 X 2

Operator Well Name Comp Date Old Total Depth

Surface pipe planned to be set 500 Conductor pipe required none Projected Total Depth 4450 feet Formation Mississippian

I certify that well will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to KCC specifications.

Date 8-10-87 Signature of Operator or Agent Charles Schmidt Title Production Manager

For KCC Use:

Conductor Pipe Required feet; Minimum Surface Pipe Required 500 feet per Alt. X

This Authorization Expires 2-11-88 Approved By 8-11-87

SPUD 8-20-87 500-8518

Approx. SW NE SW Sec. 10 Twp. 20 S, Rg. 23 X West

PLUGGING PROPOSAL IF ABOVE IS D & A

This plugging proposal will be reviewed and approved or revised at the time the district office is called prior to setting surface casing (call 7 a.m. to 5 p.m. workdays).

1st plug @ ft. deep 1535 or formation with 50 SX feet of 1160 or formation with 80 SX feet of 500 or formation with 50 SX feet of 40 or formation with 10 SX feet of

(2) Rathole to surface minus 5 feet

(b) Mousehole to surface minus 5 feet

PUSHER Rick Davis TD 4425' FORMATION Miss SURFACE PIPE 8 5/8" @ 514' ANHYDRITE ELEVATION 2269 STARTING TIME & DATE 7:00 AM 8-28-87 COMPLETION TIME & DATE 9:45AM 1st PLUG @ 1530 FT. W/ 50 SX 2nd PLUG @ 850 FT. W/ 50 SX 3rd PLUG @ 540 FT. W/ 40 SX 4th PLUG @ 40 FT. W/ 10 SX 6940 p. 4 p. 9.1 RAT HOLE CIRCULATED W/ 15 SX MURSE-HOLE CIRCULATED W/ SX WATER-WELL PLUGGED W/ SX CEMENT COMPANY Allied TECHNICIAN S.D.

RECEIVED STATE CORPORATION COMMISSION SEP 1 1987 CONSERVATION DIVISION Wichita, Kansas