

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-135-23499-00-00
Spot: SWSENE Sec/Twnshp/Rge: 10-20S-23W
2970 feet from S Section Line, 990 feet from E Section Line
Lease/Unit Name: MCCREIGHT Well Number: 2
County: NESS Total Vertical Depth: 4450 feet

Operator License No.: 32372
Op Name: BANKOFF OIL COMPANY, INC.
Address: PO BOX 700657
TULSA, OK 74170

Production Casing Size: 5.5 feet: 4448 WITH 100 SX CMT
Surface Casing Size: 8.625 feet: 326 WITH 175 SX CMT

144⁰³

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/14/2003 11:00 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: ELDON REED Company: BANKOFF OIL Phone: (620) 792-2837

Proposed Plugging Method: PUMP 200# HULLS - 35 SX CMT - 24 SX GEL - 160 SX CMT. PRESSURE TEST. CHECK BACKSIDE.

Plugging Proposal Received By: STEVE MIDDLETON WitnessType: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 10/14/2003 12:20 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:


PERFS AT 4296-4306'. PORT COLLAR @1494' WITH 400 SX CMT. PUMP DOWN 5 1/2" WITH 200# HULLS - 35 SX CMT - 24 SX GEL - 160 SX CMT. MAXIMUM PRESSURE 1000#. SHUT IN PRESSURE 1000#. PUMPED 15 SX CMT DOWN 8 5/8" X 5 1/2" ANNULUS. MAXIMUM PRESSURE 500#. SHUT IN PRESSURE 500#.

RECEIVED
OCT 22 2003
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. NO CASING RECOVERED.

Plugged through: CSG

District: 01



Signed Richard W. Lacey
(TECHNICIAN)

INVOICED
DATE 10-22-03
WEL. NO. 2004060653

[Signature]
Form CR-278