

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

RECEIVED
AUG 9 1966
CONSERVATION DIVISION
WICHITA, KANSAS

Operator's Full Name Donald C. Slawson

Complete Address: 408 One Twenty Building, Wichita, Kansas

Lease Name Lewis "B" Well No. 7

Location C SE SE Sec. 26 Twp. 20 Rge. 21 (E) (W) Y

County Ness Total Depth 4454

Abandoned Oil Well Gas Well Input Well SWD Well D & A Y

Other well as hereafter indicated:

Plugging Contractor: Co Tools

Address: License No.

Operation Completed: Hour 9 P Day 6 Month 8 Year 1966

The Above well was plugged as follows:

RTD 4454 8 5/8 csg. set at 251 cwc.

Gunned pits, circulated haeavy mud, set cementing plug at 540 Ft. and displaced
30 sc cement thru drill pipe. Heavy mud to 240 Ft. set cementing plug and displaced
20 sc cement thru drill pipe. Heavy mud to 40 Ft. set cementing plug, 1/2 sc hulls
and 10 sc cement to base of celler. Plugged rat hole with 2 sc cement.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo Maxwell
Well Plugging Supervisor

DATE 8/9/66

INV. NO. 3721-4