

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
SEP 12 1966
CONSERVATION DIVISION
WICHITA, KANSAS

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Operator's Full Name Donald C. Slawson

Complete Address: 408 One Twenty Building Wichita, Kansas

Lease Name Lewis "B" Well No. 2

Location 150' NE NE SE Sec. 26 Twp. 20 Rge. 21 (E) (W) X

County Ness Total Depth 4405'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: _____

Plugging Contractor: _____

Address: Co. Tools License No. _____

Operation Completed: Hour 8:30 P Day 8 Month 9 Year 1966

The Above well was plugged as follows:

RTD 4405' 8 5/8 csg. set at 278' cwc 225 sc.

Gunned pits, circulated heavy mud, set cementing plug at 540' and displaced
30 sc cement thru drill pipe. Heavy mud to 275' set cementing plug and
displaced 20 sc cement thru drill pipe. Heavy mud to 40' set cementing
plug, 1/3 sc hulls and 10 sc cement to base of celler. Plugged rat hole
with 2 sc cement.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Rio M. Assing
Well Plugging Supervisor

DATE 9-2-66

INV. NO. 3901-W