

R

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
AUG 21 1967
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Operator's Full Name Quality Supply Company

Complete Address: 6320 Jacqueline Wichita, Kansas

Lease Name Betz Estate Well No. 1

Location C NE SE Sec. 9 Twp. 20 Rge. 21 (E) (W) X

County Ness Total Depth 4408

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Knight Casing Pulling

Address: Box 405 Chase, Kansas License No. 436

Operation Completed: Hour 1 P Day 17 Month 8 Year 1967

The Above well was plugged as follows:

Total Depth 4408' 8 5/8 csg set at 265' cwc 175 sc/

4 1/2 csg set at 4404' cw 100 sc cement.

Filled with sand to 4380' and dumped 4 sc cement with dump bailer.

Recov. 2388' of 4 1/2 csg.

Squeezed 8 5/8 csg with 30 sc gel mud and 160 sc cement.

Mud to 680' cement (240-680) gel (50-240) Cement (50 to base of cellar)

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]
Well Plugging Supervisor

DATE 8-21-67

INV. NO. 6165-W