


15.135.19181.0000

Form CP-3  
Rev. 6-26-62

 KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
OCT 17 1966  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Operator's Full Name Quality Oil Company

Complete Address: 6320 Jacqueline Wichita, Kansas

Lease Name Beltz Well No. 1

Location C SE NE Sec. 9 Twp. 20 Rge. 21 (E) (W) X

County Ness Total Depth 4390'

Abandoned Oil Well X Gas Well      Input Well      SWD Well      D & A     

Other well as hereafter indicated:     

Plugging Contractor: Knight & Casing Pulling Co.

Address: Box 405 Chase, Kansas License No. 436

Operation Completed: Hour 5 P Day 13 Month 10 Year 1966

The Above well was plugged as follows:

Total Depth 4390' 8 5/8 csg set at 511' cwc 280 sc.

4 1/2 csg set at 4387' cw 100 sc.

Sand back to 4350'--Dumped 4 sc cem. with dump bailer.

Recov. 2700' of 4 1/2 csg.

Pumped 100 sc cement plug to 530'- Top of cement at 200'.

Mud to 75'--Pumped 25 sc cement to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed:   
Well Plugging Supervisor

DATE 10/14/66

INV. NO. 4111-w