

Y
KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION
MAR 6 - 1968
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Mobil Oil Corporation

Complete Address: P. O. Box 1934 Oklahoma City, Okla.

Lease Name Betz Estate Well No. 1

Location App. C SE SE Sec. 9 Twp. 20 Rge. 21 (E) (W) X

County Ness Total Depth 4431

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Glenn & Smith Pulling Co.

Address: 204 E. 6th Ellinwood, Ks. License No. 396

Operation Completed: Hour 10 A Day 2 Month 3 Year 1968

The Above well was plugged as follows:

Total Depth 4431' 8 5/8 csg set at 503' cwc.

5 1/2 csg set at 4424' cw 200 sc cement.

Filled with sand to 4400' and dumped 5 sc cement with dump bailer.

Recov. 2960' of 5 1/2 csg.

Set 10' rock bridge and 25 sc cement plg at 500'.

Filled with mud to 50' set 10' rock bridge and filled to surface with 10 sc cement.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Ken F. Messer
Well Plugging Supervisor

DATE 3/6/68

INV. NO. 7368-W