

KANSAS

FORM CP-3  
Rev. 11-3-80

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

API Number 15-145-20420.0000

245 North Water  
Wichita, KS 67202

Operator's Full Name C + G. DRILLING COMPANY

Complete Address BOX 158 GARFIELD, KANSAS 67529

Lease Name THOMPSON Well No. #1

Location NW - NW Sec. 9 Twp. 20 Rge. 20 (East) (West)

County PAWNEE Total Depth 4333 FE

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated \_\_\_\_\_

Plugging Contractor MELSO CASING PULLING (GENE SMITH)

Address BOX 176 CHASE, KS. License No. \_\_\_\_\_

Operation Completed: Hour 11:00 Day 20 Month FEB Year 1981

The above well was plugged as follows:

8 5/8" 250 FE SP. CUM W/ 140 ST -> 5 1/2" SET AT. 4330 FE W/ 145 ST.  
PERF'S OPEN HOLE -> PIPE PULLERS COULD ONLY GET DOWN TO 3960 FE  
BOTTOM CAVED IN - SHOT TWICE. RECOVERED 2320 FE PIPE.  
ORDERED 140 ST 50/50 PERMIX 6% GEL -> 25 ST GEL -> 6 ST HULL'S - 2 3/8" PLUG.  
PUMPED IN WITH PUMP TRUCK.  
PUMPED IN 8 5/8" - 3 ST HULL'S - 8 ST GEL. RELEASED PLUG. AND  
140 ST CUM. MAX. PRESSURE 950 LBS - SHUT IN 550 LBS  
CEMENTED BY ALLIED OMT.

2-23-81

I hereby certify that the above well was plugged as herein stated.

**INVOICED**  
DATE 3-4-81  
INV. NO. 4722-W

Signed: [Signature]  
Conservation Division Agent  
FEB 23 1981  
CONSERVATION DIVISION  
Wichita, Kansas