

15.145.2005.0000

Form CP-3  
Rev. 6-26-62

KANSAS

10

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

APR 4 1967

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Operator's Full Name Pickrell Drilling Company

Complete Address: 705 Fourth National Bank Bldg. Wichita, Kansas

Lease Name Lanternman "A" Well No. 1

Location C NE SE Sec. 9 Twp. 20 Rge. 20 (E) (W) X

County Pawnee Total Depth 4340'

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A X

Other well as hereafter indicated:     

Plugging Contractor: Co. Tools

Address:      License No.     

Operation Completed: Hour 2:45 P Day 3 Month 4 Year 1967

The Above well was plugged as follows:

RTD 4340 8 5/8 csg set at 280' cwc 165 sc.

Gunned pits, circulated heavy mud, set cementing plug at 550' and displaced 25 sc cem.

thru drill pipe. Heavy mud to 260' set cementing plug and displaced 20 sc cement thru

drill pipe. Heavy mud to 40' set cementing plug, 1/2 sc hulls and 8 sc cement to base

of cellar. Plugged rat hole with 2 sc cement.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: R. J. Massey  
Well Plugging Supervisor

DATE 4/4/67

INV. NO. 4999-W