

15.145.20147.0000

Form CP-3  
Rev. 6-4-68

KANSAS

*10*

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

RECEIVED  
STATE CORPORATION COMMISSION  
APR 19 1971  
CONSERVATION DIVISION  
Wichita, Kansas

*7-0 4 7*

Operator's Full Name J. A. Allison

Complete Address 1115 Wichita Plaza Wichita, Kansas 67202

Lease Name Fox "B" Well No. 1

Location NW NE NE Sec. 36 Twp. 20 Rge. (E) (W) 19

County Pawnee Total Depth 4095'

Abandoned Oil Well XX Gas Well        Input Well        SWD Well        D & A       

Other well as hereafter indicated       

Plugging Contractor Ralph Comstock

Address Stafford, Kansas License No. 490

Operation Completed: Hour 11:30 A Day 17 Month 4 Year 1971

The above well was plugged as follows:

Total Depth 4095' 8 5/8 csg set at 368' cwc 180 sk.

5 1/2 csg set at 4094' cw 100 sk cmt.

5 1/2 csg perf. (3906')

Set 5 1/2 wood plug at 3850' --poured 25' sd and dumped 5 sk cmt W/dump bailer. (3800-3850)

Cutoff and recovered 2060' of 5 1/2 csg.

Pumped down 8 5/8 csg with 12 sk gel W/5 sk hulls --100 sk poz 6% --8 sk gel --release

plug and pumped 20 sk poz 6%. Max. pres. 1500 lbs. SI pres. 1500 lbs.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *L. G. Muesel*  
Well Plugging Supervisor

DATE 4/20/71

INV. NO. 3599-W