

KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

MAY 14 1963

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Operator's Full Name Santa Fe Pipe & Supply

Complete Address: Box 562 Great Bend, Kans

Lease Name ~~Molde~~ *Nolde* Well No. 1

Location SE SE NW Sec. 34 Twp. 20 Rge. (E) (W) 19

County Pawnee Total Depth 4450

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A X

Other well as hereafter indicated:     

Plugging Contractor: Ace Pipe Pulling

Address: Great Bend, Kans License No. 2

Operation Completed: Hour 6PM Day 11 Month 5 Year 62

The Above well was plugged as follows:

8 5/8" 338' circulated with cement - 4 1/2" 4450' with 200 sax cement.

PB to 4388' - perf 4322

Sand back to 4300', set 4 sax cement with dump bailer - pulled 3221'

4 1/2" 450', circulated hole with heavy gel mud, displaced 20 sax cement

through 4 1/2" at 450', heavy mud to 225', displaced 20 sax cement through

4 1/2" - heavy mud to 35', cement to bottom cellar.

Mudding and cementing by Ace Pipe Pulling pump truck.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *Edson Petty*  
Well Plugging Supervisor

DATE 5/14/62

INV. NO. 7092-W