

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
Form CP-3
STATE CORPORATION COMMISSION
6-4-68

OCT 21 1977

CONSERVATION DIVISION
Wichita, Kansas

R

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 -145-20435.0000 (of this well)

Operator's Full Name Brougner Oil, Inc.

Complete Address Drawer 1367, Great Bend, Kansas 67530

Lease Name Thurman Well No. 1

Location C SW SW Sec. 33 Twp. 20 Rge. (E) (W) 19

County Pawnee Total Depth 4277'

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Kelso Casing Pulling

Address Box 176, Chase, Kansas 67524 License No. 683

Operation Completed: Hour 2:45 P Day 18 Month 10 Year 1977

The above well was plugged as follows:

Total Depth 4277' 8 5/8 csg set 384' cwc 225 sk.

4 1/2 csg set 4277' cw 150 sk cem.

4 1/2 csg PBSD 4265' with top perf. (4245')

Filled 4 1/2 csg W/sd (4265'-4200') dumped 4 sk cem W/dump bailer. (4200'-4165')

Cutoff & recovered A/3200' of 4 1/2 csg.

Halliburton Cementing Co. mixed & pumped down 8 5/8 csg with 25 sk gel & water-

followed with cementing plug & 120 sk 50-50 poz cem. 6% gel & shutin. FPP 650 lbs.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo Messing
Well Plugging Supervisor

DATE 10-21-77

INV. NO. 6066-W