

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Operator's Full Name Petroleum Operating Co.

Complete Address: 6045 Pine Tree Drive Miami Beach, Florida

Lease Name Kurt Well No. 1

Location SW - NW Sec. 27 Twp. 20 Rge. 19 (E) (W) X

County Pawnee Total Depth 4380

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: _____

Plugging Contractor: H-30 Drilling Co.

Address: Wichita, Kansas License No. _____

Operation Completed: Hour 5 30 A Day 29 Month 5 Year 1966

The Above well was plugged as follows:

RTD 4380 85/8 at 388 cw 250 sc. cement.

Gunned pits. circulated heavy mud, set cementing plug at 540 Ft. and displaced
25 sax cement thru drill pipe. Heavy mud to 375 Ft. and displaced 20 sax cement
thru drill pipe. Heavy mud to 40 Ft. built solid bridge of cementing plug, 1/3 sax
hulls, and 10 sax cement to base of cellar. Plugged rat hole with 2 sax cement.

RECEIVED
STATE CORPORATION COMMISSION
5-31-66

I hereby certify that the above well was plugged as herein stated.

INVOICED

CONSERVATION DIVISION
Wichita, Kansas
Signed: Leo Messing
Well Plugging Supervisor

DATE 5/31/66
INV. NO. 3306-U