

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-135-20461-00.00

LEASE NAME YOUNT

WELL NUMBER #1

1920 Ft. from S Section Line

1920 Ft. from W Section Line

SEC. 8 TWP. 20S RGE. 21 (~~XX~~or W)

COUNTY NESS

Date Well Completed 9/17/71

Plugging Commenced 08/21/03

Plugging Completed 08/22/03

RECEIVED

SEP 29 2003

KCC WICHITA

LEASE OPERATOR FALCON EXPLORATION, INC.

ADDRESS 155 N. MARKET, STE 1020; WICHITA, KS 67202

PHONE#(316-262-1378 OPERATORS LICENSE NO. 5316

Character of Well OIL

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on AUGUST 20, 2003 (date)

by DAVID P. WILLIAMS (KCC District Agent's Name).

Is ACO-1 filed? DO NOT HAVE IN FILE If not, is well log attached? YES

Producing Formation MISSISSIPPI Depth to Top 4425 Bottom 4432 T.D. 4436

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
MISSISSIPPI	O & W	4425	4432	8 5/8	376	0
				5 1/2	4426.5	0
				2 3/8	NA	144 JTS.

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. put 1200 lbs sand down casing, let set over night; tagged bottom at 4300', put 4 sx cement on bottom; pressure casing to 400 psi - held; perforate at 725'; mix 80 sx light 60/40 poz 6% gel cement and pump down hole; mix 60 sx light 60/40 poz 6% gel cement w/ 200# hulle and pump down hole; *finish w/ 150 sx light 60/40 poz 6% gel cement in braden head; held at 250psi *tied to (If additional description is necessary, use BACK of this form.)
backside and

Name of Plugging Contractor PLAINS, INC. License No. 4072

Address P.O. BOX 346; NESS CITY, KS 67560

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: FALCON EXPLORATION, INC.

STATE OF KANSAS COUNTY OF SEDGWICK, ss.

MICHEAL S. MITCHELL (Employee of Operator) or ~~X~~ of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]

MICHEAL S. MITCHELL

(Address) 155 N. MARKET, STE 1020; WICHITA, KS

SUBSCRIBED AND SWORN TO before me this 25TH day of SEPTEMBER, 19 2003

Rosann M Schippers

My Commission Expires: 9/28/2007




15.135.20461.0000

RECEIVED
SEP 29 2003
KCC WICHITA

WILDCAT

9-134 Map. No. _____ REPL #1
OPER RAY STEKOLL & ASSOCIATES
214 PAGE COURT, WICHITA, KS
WELL #1 YOLNT
CONTR SAGE DRLG CO.
WC 1/2 MI SW/BETZ WEST (MISS)
IP CO IPP 15 BOPD + 6% WTR, MISS 4426-36
API #15-135-20461
PTD 4450



S-T-R 8-20S-21W WF
INIT
SPOT C NE SW
CO NESS, KS WFD
ELEV 2268 KB FIN

SPUD 7-21-71, 8 5/8" @376 W/200
NO CORES
DST 1 (MISS) 4408-29, OP 75 MIN, REC 210' OCM, ISIP 1242/
30 MIN, IFP 83, FFP 120, FSIP 1195/30 MIN
DST 2 (MISS) 4413-32, OP 75 MIN, REC 240' OCM, ISIP 1214/
30 MIN, IFP 102, FFP 139, FSIP 1177/30 MIN
RTD 4432, LOG 5 1/2" @4426 W/100
MICT, CO DD 4432, DUMP 1 BBL ACID, SWAB 1/2 BOPH, DD
4434, DUMP 1 BBL ACID, SWAB 1 BOPH, DD 4436 TD, SWAB 2/3
BFPH, 5% WTR, POP, CO IPP 15 BOPD + 6% WTR, MISS 4426-36
COMPLETED 9-17-71
CORRECTION ON OPERATOR: WAS BRANDT AND CLARK, HOWEVER,
RAY STEKOLL & ASSOCIATES ASSUMED OPERATIONS AT CASING
POINT.
REPLACES COMP ISSUED 9-23-71
REPLACED TO CORRECT KB ELEV; WAS-2768 KB; IS-2268 KB;
AND ALSO TO CORRECT ALL LOG TOP MINUS DATUMS
EXTENSION OF BETZ WEST (MISS)

KB LOG TOPS
STONE CORRAL
1485 + 783
HEEBNER 3783 -1515
TORONTO 3801 -1533
LANSING 3829 -1561
BASE KANSAS CITY
4163 -1895
MARMATON 4177 -1909
FORT SCOTT 4327 -2059
CHEROKEE 4350 -2082
CONGLOMERATE
4381 -2113
MISS OSAGE 4425 -2157
LTD 4432 -2164
RTD 4432 -2164
DDTD 4436 -2168
TD IN MISS FORM
REPL COMP ISSUED 10-14-71

Petroleum Information Corporation.
A Subsidiary of A. C. Nielsen Company



15-135-20461-0000

CHARGE TO:
FALCON EXPLORATION
 ADDRESS
 CITY, STATE, ZIP CODE

TICKET

No 5867

PAGE 1 OF 1

RVCE LOCATIONS NESS CITY, KS	WELL/PROJECT NO. #1	LEASE YOUNT	COUNTY/PARISH NESS	STATE Ks	CITY	DATE 8-22-03	OWNER SAME
TICKET TYPE <input checked="" type="checkbox"/> SERVICE <input type="checkbox"/> SALES	CONTRACTOR PLAINS W/ SERVICE	RIG NAME/NO.	SHIPPED VIA CT	DELIVERED TO LOCATOR	ORDER NO.		
WELL TYPE 02	WELL CATEGORY ARABIAN	JOB PURPOSE PTA	WELL PERMIT NO.	WELL LOCATION BAZOK - 8S, 1 1/4 E, NS			
FERRAL LOCATION	INVOICE INSTRUCTIONS						

PRICE REFERENCE	SECONDARY REFERENCE/ PART NUMBER	ACCOUNTING			DESCRIPTION	QTY.		UNIT PRICE		AMOUNT
		LOC	ACCT	DF		QTY.	U/M	QTY.	U/M	
575		1			MILEAGE * 104	20	ME		2.50	50.00
576		1			PUMP SERVICE	1	JOB		550.00	550.00
275		1			COTTON SEED HULLS	2	SLS	200	20.00	40.00
328		1			SWEPT LIGHT 60/40-POZ MAX (6% GEL)	290	SLS		5.90	1711.00
581		1			SERVICE CHARGE C/MOT	290	SLS		1.00	290.00
583		1			DRAINAGE	24803	USS	248.03	.85	210.83

RECEIVED
 SEP 2 9 2103
 KCC MICHITA

LEGAL TERMS: Customer hereby acknowledges and agrees to the terms and conditions on the reverse side hereof which include, but are not limited to, **PAYMENT, RELEASE, INDEMNITY,** and **LIMITED WARRANTY** provisions.

TO BE SIGNED BY CUSTOMER OR CUSTOMER'S AGENT PRIOR TO START OF WORK OR DELIVERY OF GOODS

[Signature]
 SIGNED **8-22-03** TIME SIGNED **1630** A.M. P.M.

REMIT PAYMENT TO:
SWIFT SERVICES, INC.
P.O. BOX 466
NESS CITY, KS 67560
785-798-2300

SURVEY	AGREE	UN-DECIDED	DIS-AGREE	PAGE TOTAL	2851 83
OUR EQUIPMENT PERFORMED WITHOUT BREAKDOWN?					
WE UNDERSTOOD AND MET YOUR NEEDS?				TAX	151 15
OUR SERVICE WAS PERFORMED WITHOUT DELAY?					
WE OPERATED THE EQUIPMENT AND PERFORMED JOB CALCULATIONS SATISFACTORILY?				TOTAL	3002 98
ARE YOU SATISFIED WITH OUR SERVICE? <input type="checkbox"/> YES <input type="checkbox"/> NO					
<input type="checkbox"/> CUSTOMER DID NOT WISH TO RESPOND					

CUSTOMER ACCEPTANCE OF MATERIALS AND SERVICES The customer hereby acknowledges receipt of the materials and services listed on this ticket.

OPERATOR **WAVE WILSON** APPROVAL

Thank You!

JOB LOG

SWIFT Services, Inc.

DATE 8-22-03 PAGE NO. 1

CUSTOMER FALCON EXPLORATION WELL NO. # 1 LEASE YOUNT JOB TYPE PTA TICKET NO. 5867

CHART NO.	TIME	RATE (BPM)	VOLUME (BBL) (GAL)	PUMPS		PRESSURE (PSI)		DESCRIPTION OF OPERATION AND MATERIALS
				T	C	TUBING	CASING	
	1430							ON LOCATION
								RECEIVED
								5 1/2 - PERFS @ 725'
								8 5/8 - 376'
								KCC WICHITA
	1440	2	4		✓	500		WJ RATE
	1505	3 ^{AJG}	24		✓	500		MAX 80 SKS COMWT 700'
	1515							SHUT DOWN - PSE SLOW BLEED OFF
	1525	3	18		✓	500		MAX 60 SKS COMWT W/200# HULLS
	1531							SHUT DOWN - 150 PSE - SHUT 2J
	1540	2	44 1/2		✓	500 ^{max}		MAX 150 SKS COMWT - BRANCH HEAD
	1610							SHUT DOWN - HOLDING 250 PSE - SHUT 2J
								WASH UP
	1700							JOB COMPLETE
								THANK YOU
								WAVE, DUSTY, SHINE

Plains, Inc.

P.O. Box 346
Ness City, KS 67560
Phone 785-798-3995

RECEIVED

SEP 29 2003
KCC WICHITA

WORKTICKET

NEW WELL No 8978

OLD WELL

RIG # 6 DATE 09/22/03

COMPLETE

INCOMPLETE

JOB TYPE plug job

COMPANY Falcon

LEASE Yount

WELL# 1

ADDRESS _____

SEC _____

TWP _____

ANG _____

CITY/STATE _____

ZIP CODE _____

COUNTY Ness

STATE KS

POSITION	NAME	HRS	REVENUE	TRAVEL	NONREVENUE	TOTAL HRS	WKD
OPERATOR	Gilbert	9 1/2		2		10	
DERRICKHAND	Philip	9 1/2		2		10	
FLOORHAND	Swan	9 1/2		2		10	
FLOORHAND	Jesse	9 1/2		2		10	

JTS	PULLED	WELL EQUIPMENT	JTS	RAN
		POLISHED RODS		
		PONY RODS		
		RODS		
		RODS		
		RODS		
		PUMP / VALVES		
		PUPS		
		TUBING		
		SN / BBL		
		ANCHOR / PACKER		
		OTHER		

DESCRIPTION OF WORK BEING PERFORMED

Drags to location rigged up for plugging down tagged bottom, bottom was at 4300 tripped in with bailer 4 times 1 sack of concrete at a time. Water truck pressured up on casing to 400 psi casing held waited on loggers, loggers parted at 700' Swift circulated rigged down moved off.

RIG W/2 MEN	9 1/2	HRS@	135.00	PER HOUR	TOTAL	1282.50
TRAVEL TIME	2	HRS@	100.00	PER HOUR	TOTAL	50.00
SWAB CUPS NO.	SIZE	TYPE	PER EACH	TOTAL		
SWAB CUPS NO.	SIZE	TYPE	PER EACH	TOTAL		
OIL SAVER RUBBERS			PER EACH	TOTAL		
DOPE			PER EACH	TOTAL		
TUBING TONGS				TOTAL		
ROD TONGS				TOTAL		
REVERSE CIRC. & SWIVEL				TOTAL		
OUT OF TOWN				TOTAL		
MISC. <u>Pump bailer</u>				TOTAL		75.00
X _____				TOTAL		1407.50
COMPANY REPRESENTATIVE		DATE				