

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

Ness County, Sec. 18 Twp. 20 Rge. 21 (E) W (W)

Location as "NE/CNW/SW" or footage from lines SW SW NE

Lease Owner Pickrell Drlg. Co.; Wichita, Kans. 67202

Lease Name Wittman Well No. C #1

Office Address 705 4th National Bank Bldg.

Character of Well (completed as Oil, Gas or Dry Hole) Oil

Date well completed May 27 19 69

Application for plugging filed June 22 19 70

Application for plugging approved June 22 19 70

Plugging commenced June 22 19 70

Plugging completed June 25 19 70

Reason for abandonment of well or producing formation Depleted

If a producing well is abandoned, date of last production June 5 19 70

Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well Leo Massey

Producing formation Cherokee Depth to top 4333 Bottom -- Total Depth of Well 4440 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	269	NONE
				5 1/2	4435	3091

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

June 22, 1970 Plugged off bottom. Dumped sand to 4350'. Mixed and dumped 5 sx of cement to 4310'.

June 25, 1970 Globe Oil Well Cementing Co. mixed and pumped down 8 5/8" surface casing:
12 sx gel and 2 sx hulls
50 sx cement
8 sx gel
Released plug and 50 sx of cement
(cement contained 6 % gel)

RECEIVED
STATE CORPORATION COMMISSION
JUL 6 1970
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor RUSS CASING PULLING, INC.
Address P. O. Box 1082 Great Bend, Kansas 67530

STATE OF Kansas COUNTY OF Sedgwick, ss.
Dale M. Robinson (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Dale M. Robinson
705 Fourth National Bank Bldg, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 2nd day of July, 19 70
Jan. 19, 1973
Esther Lamone
Notary Public.



ROTARY DRILLING LOG

COMPANY: Pickrell Drilling Company
705 4th National Bank Bldg.
Wichita, Kansas 67202

Rotary Drilling Commenced 4/27/69
Rotary Drilling Completed 5/6/69

LOCATION: Wittman "C" No. 1
SW SW NE Sec. 18-20S-21W, Ness County, Kansas

CONTRACTOR: **PICKRELL DRILLING COMPANY**
Wichita, Kansas

CASING RECORD: Ran 15 jts. used 8 5/8" casing set @ 269' KB. Cemented with 165 sacks cement. Circulated. Completed 7:00 PM, April 27, 1969.

Ran 141 jts. 5 1/2" casing set 5' off bottom at 4435'. Cemented with 100 sacks common cement. Plug down 1:20 PM, May 7, 1969.

LOG

(Figures indicate bottom of formation — measurements from top of rotary bushing.)

140	Post Rock	<u>C. F. S.</u>
270	Shale & Shells	4340
635	Shale	4392
885	Shale & Red Bed	4402
1090	Sand	4406
1445	Shale, Shells & Sand	4420
1482	Anhydrite	4440
1840	Shale	
2299	Shale & Lime	<u>Slope Tests</u>
2770	Lime & Shale	2000
2900	Shale & Lime	2500
3070	Shale	3000
3870	Shale & Lime	3500
3975	Lime & Shale	4000
4235	Lime	
4290	Lime & Shale	
4340	Shale & Lime	
4392	Lime & Shale	<u>S.L.M.</u>
4419	Sand	
4440	Mississippian RTD	

RECEIVED
STATE CORPORATION COMMISSION
JUN 23 1970
CONSERVATION DIVISION
Wichita, Kansas

The undersigned, C. W. Sebitts, Attorney-in-Fact for PICKRELL DRILLING COMPANY, hereby certifies in behalf of said Company, that the above is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Reports.

PICKRELL DRILLING COMPANY
By [Signature]
C. W. Sebitts Attorney-in-Fact

STATE OF KANSAS }
COUNTY OF SEDGWICK } ss.:

On this 14th day of May, 1969, before me the undersigned, a Notary Public, in and for the County and State aforesaid, personally appeared C. W. Sebitts, to me known to be the identical person who subscribed the name of PICKRELL DRILLING COMPANY to the foregoing instrument as its Attorney-in-Fact and acknowledged to me that he executed the same as his free and voluntary act and deed, and as the free and voluntary act and deed of such company, for the uses and purposes therein set forth.

Given under my hand and seal of office the day and year last above written.

My commission expires: May 10, 1970

[Signature]
L. M. Whiting Notary Public