

15.135.30209.0001

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 2-18-72

LEASE NAME Lewis

WELL NUMBER #2 (OWWO)

SPOT LOCATION 6 NW NE

SEC. 26 TWP. 20 RGE. 21 (E) or (W)

COUNTY Ness

Date Well Completed _____

Plugging Commenced 7-2-84

Plugging Completed _____

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Four-Way Operating, Inc.

ADDRESS Box 698, Great Bend, Ks. 67530

PHONE # (792)-2506 OPERATORS LICENSE NO. 5310

Character of Well oil
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? One

Is ACO-1 filed? _____ If not, is well log attached? With application

Producing formation _____ Depth to top _____ bottom T.D. 1212'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8"	350'	None
				5-1/2"	1210'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set. Squeezed well with 3 sacks hulls, 6 sacks gel and 50 sacks 60/44 pozmix cement with 2% added gel and 3% calcium chloride. Maximum pressure was 1300 psi and shut in 100 psi.

Name of Plugging Contractor Rockhold Engineering, Inc. License No. 5111
Address Box 698, Great Bend, Ks. 67530

STATE OF Kansas COUNTY OF Barton, ss.

James W. Rockhold (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) James W. Rockhold
James W. Rockhold
(Address) Box 698, Great Bend, Ks.

RECEIVED
STATE CORPORATION COMMISSION

JUL 17 1984

SUBSCRIBED AND SWORN TO before me this 16th day of July, 1984

CONSERVATION DIVISION
Wichita, Kansas
My Commission expires: _____

STATE NOTARY PUBLIC
KANSAS
IONA M. LEATHERMAN
Barton-County, Kansas
My Appt. Exp. 9-26-87

Iona M. Leatherman
Notary Public

DRILLER'S LOG

COMPANY: O. A. Sutton, 407 Insurance Bldg., Wichita, Kansas
 CONTRACTOR: Hellar Drilling Company, Inc., Wichita, Kansas
 LEASE: #2 Lewis
 LOCATION: 125' South of C NW NE Sec. 26-20S-21W, Ness County, KS
 COMMENCED: June 18, 1966
 COMPLETED: June 29, 1966
 CASING: Set 8 5/8" surface casing @ 350'/250 sacks cement

0-350	Surface sand & soil
350-1398	Shale, shell, sand & Red Bed
1398-1428	Anhydrite
1428-1884	Shale, Red Bed & shells
1884-2408	Salt Section
2408-2575	Ft. Riley cherty lime
2575-2854	Lime & shale
2854-3552	Shale & lime
3552-3811	Lime & shale
3811-3930	Lsg. K.C.
3930-4073	Lime
4073-4315	Lime & shale
4315-4359	Lime, shale & cherty lime
4359-4369	Cherty Cong.
4369-4474	Miss. chert
4474-4477	Lime
4477	Rotary Total Depth

D & A

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

I, D. L. Hellar, do hereby certify that the above and foregoing is a true and correct copy of the log of the #2 Lewis; located 125' South of C NW NE Sec. 26-20S-21W, Ness County, Kansas, as reflected by the files of the Hellar Drilling Company, Inc.

HELLAR DRILLING COMPANY, INC.

By *D. L. Hellar*
 President - D. L. Hellar

Subscribed and sworn to before me, a Notary Public, in and for Sedgwick County, Kansas, this 5th day of July, 1966.

My Commission Expires:

Catherine Darcey
 Notary Public - Catherine Darcey

March 25, 1968.

RECEIVED
 STATE CORPORATION COMMISSION

MAY 17 1984

CONSERVATION DIVISION
 Wichita, Kansas