

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15.135.30253.0000

API NUMBER 6-17-66

LEASE NAME Lewis

WELL NUMBER #1

SPOT LOCATION C SE NE

SEC. 26 TWP. 20 RGE. 21 (E) or (W)

COUNTY Ness

Date Well Completed

Plugging Commenced 6-27-84

Plugging Completed 7-2-84

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Four-Way Operating, Inc.

ADDRESS Box 698, Great Bend, Ks. 67530

PHONE # (792-2506) OPERATORS LICENSE NO. 5310

Character of Well oil
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? 1

Is ACO-1 filed? If not, is well log attached? With application

Producing formation Depth to top bottom T.D. 4361'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8"	345'	None
				5-1/2"	4,356'	278.43'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set. Dumped sand to 4300' and 5 sacks cement. Shot casing at 700', 500' and 300'. Pulled 9 joints of 5-1/2" casing. Squeezed well with 2 sacks hulls, 7 sacks gel and 200 sacks 60/40 pozmix with 2% added gel and 3% calcium chloride. Maximum pressure was 1300 psi and shut in 100 psi.

Name of Plugging Contractor Rockhold Engineering, Inc. License No. 5111
Address Great Bend, Ks. 67530

STATE OF Kansas COUNTY OF Barton, ss.

James W. Rockhold (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct. Help me God.

(Signature) James W. Rockhold
James W. Rockhold
(Address) Box 698, Great Bend, Ks.

JUL 17 1984

CONSERVATION DIVISION
Wichita, Kansas

My Commission expires:

SUBSCRIBED AND SWORN TO before me this 16th day of July, 1984
Iona M. Leatherman
Barton County, Kansas
My Appt. Exp. 7-26-87

Notary Public

GABBERT-JONES, INC.
 WICHITA, KANSAS
 DRILLERS' WELL LOG


LEWIS #1
 C SE NE SECTION 26-20S-21W
 NESS COUNTY, KANSAS

COMMENCED: JUNE 3, 1966
 COMPLETED: JUNE 12, 1966

OPERATOR - O. A. SUTTON

DEPTH		FORMATION	REMARKS
FROM	TO		
0	345	SURFACE SOIL AND SHALE	RAN 10 JOINTS 8-5/8" CASING, SET @ 345' w/250 SACKS CEMENT.
345	1390	RED BED AND SHALE	
1390	1475	ANHYDRITE	
1475	1845	SHALE AND SHELLS	
1845	2450	SHALE AND LIME	
2450	2875	LIME	
2875	3900	LIME AND SHALE	
3900	4215	LIME	
4215	4315	LIME AND SHALE	
4315	4359	LIME	
4359	TD		RAN 134 JOINTS OF 5 1/2" CASING, SET @ 4356' w/100 SACKS CEMENT.

I, E. E. HALL, CERTIFY THIS IS A CORRECT COPY OF THE DRILLERS' LOG FOR THE WELL DRILLED IN THE C SE NE SECTION 26-20S-21W, NESS COUNTY, KANSAS, TO THE BEST OF MY KNOWLEDGE AND BELIEF.




 E. E. HALL

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

BEFORE ME, THE UNDERSIGNED, A NOTARY PUBLIC WITHIN AND FOR SAID COUNTY AND STATE, ON THIS 14TH DAY OF JUNE, 1966, PERSONALLY APPEARED E. E. HALL, TO ME PERSONALLY KNOWN TO BE THE IDENTICAL PERSON WHO EXECUTED THE WITHIN AND FOREGOING INSTRUMENT AND ACKNOWLEDGED TO ME THAT HE EXECUTED THE SAME AS HIS FREE AND VOLUNTARY ACT AND DEED FOR THE USES AND PURPOSES THEREIN SET FORTH.

IN WITNESS WHEREOF, I HAVE HEREUNTO SET MY HAND AND OFFICIAL SEAL THE DAY AND YEAR LAST ABOVE WRITTEN.



 BARBARA J. LAYTON, NOTARY PUBLIC

My Commission Expires February 1, 1968.

RECEIVED
 STATE CORPORATION COMMISSION
 MAY 17 1984
 CONSERVATION DIVISION
 Wichita, Kansas