

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

WELL PLUGGING RECORD

T 20S NORTH R 20W

*			
	20		

Locate well correctly on above
Section Plat

Pawnee County, Sec. 22 Twp. 20S Rge. 20W (E) (W)

Location as "NE/CNW/SW" or footage from lines NE NW NW
 Lease Owner R. W. Rine Drilling Company
 Lease Name Draper Well No. 1
 Office Address 320 Central Building - Wichita, Kansas
 Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
 Date well completed November 1 19 55
 Application for plugging filed November 25, 19 55
 Application for plugging approved November 28, 19 55
 Plugging commenced November 25 19 55
 Plugging completed December 3 19 55
 Reason for abandonment of well or producing formation dry

If a producing well is abandoned, date of last production none 19
 Was permission obtained from the Conservation Division or its agents before plugging was com-
 menced? Yes

Name of Conservation Agent who supervised plugging of this well R. L. Brundage
 Producing formation Depth to top Bottom Total Depth of Well 4481 Feet
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	310'	None
				5-1/2"	4349'	2429'
				Plug set at 4283' and pipe perforated at 4270'.		

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled the hole with sand from 4283' to 4260' and ran 5 sacks of cement. Mudded the hole to 300', set a 10' rock bridge and ran 20 sacks of cement at 290'. Mudded the hole to 40', set a 10' rock bridge and ran 10 sacks of cement on top. Plugging Completed.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor West Supply Co., Inc.
 Address Chase, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Paul A. Harper (employee of owner) or (~~owner~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Paul A. Harper (Paul A. Harper)

The R. W. Rine Drilling Co., 320 Central Bldg. Wichita, Kansas. (Address)

SUBSCRIBED AND SWORN to before me this 14th day of December, 19 55

Frances C. Newlon
 Frances C. Newlon Notary Public.

My commission expires October 23, 1957

PLUGGING
 FILE SEC 22 T 20 R 30W
 BACK PAGE 19 LINE 26

DEC 15 1955
 12-15-55
 CONSERVATION DIVISION
 WICHITA, KANSAS

KANSAS GEOLOGICAL SOCIETY
 KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
 KANSAS GEOLOGICAL SOCIETY BUILDING
 508 EAST MURDOCK - WICHITA, KANSAS

15.145.00398.0000

COMPANY **Kine Drilling Company, et al**


SEC. 22 T. 20S R. 20W

FARM **Draper** NO. **1**

LOC. **NE SW 13**

TOTAL DEPTH **4480'**
 COMM. **10/11/55** COMP. **11/1/55**
 SHOT OR TREATED
 CONTRACTOR **Armer, Inc.**
 ISSUED

COUNTY **Pawnee**
 KANSAS



CASING

20	10	
15	8	309'
12	6	
13	5	4349'

ELEVATION **2215 K.F.**

PRODUCTION

FIGURES INDICATE BOTTOM OF FORMATIONS

Post Rock	40
Shale & Shells	200
Sand	240
Shale & Shells	309
Shale	783
Sand	1010
Red Bed, Shale & Shells	1305
Red Bed	1355
Anhydrite	1385
Shale, Shells & Red Bed	1820
Shale & Shells	2110
Shale & Lime	2240
Lime	2630
Lime & Shale	2705
Shale & Lime	3140
Lime	3565
Shale & Lime	3765
Lime	4030
Shale & Lime	4075
Lime	4120
Shale & Lime	4210
Shale & Sand	4230
Shale & Lime	4275
Lime & Chert	4301
Chert & Cherty Lime	4333
Lime & Shale	4359
Lime, Shale & Sand	4405
Cherty Lime	4425
Lime	4475
Granite	4480

FORMATION TYPES

HUBBARD	3644
TORONTO	3664
LANSING	3696
PENN. CONGLOMERATE	4192
MISSISSIPPI	4260
MISNER	4370
VIOLA	4408
PRE. CANADIAN	4473

RECEIVED
 STATE CORPORATION COMMISSION
 NOV 26 1955
 CONSERVATION DIVISION
 Wichita, Kansas

I hereby certify that this is a true and correct log of the above described well as shown by the drilling reports.

ARMER, INC.

By Merle Britting

STATE OF KANSAS }
 } SS:
 COUNTY OF SMOCKLEY }

Subscribed and sworn to before me, a notary public in and for said County and State this 3rd day of November, 1955.

Rose Turey
 Notary Public

My Commission expires February 13, 1956.

PLUGGING
 FILE REC 227 20R 20W
 BOOK PAGE 19 LINE 26