

KANSAS

Form CP-3  
Rev. 6-4-68

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
245 North Water  
Wichita, KS 67202

API Number 15 - 135-21300-0000 (of this well)

RECEIVED  
STATE CORPORATION COMMISSION  
JUN 07 1977  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Abercrombie Drilling, Inc.  
Complete Address 801 Union Center, Wichita Kansas  
Lease Name Mollie Moore Well No. 1  
Location C SW NW Sec. 8 Twp. 20 Rge. (E) (W) 21  
County Ness Total Depth 4416'  
Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A   
Other well as hereafter indicated \_\_\_\_\_  
Plugging Contractor Pipe Pullers, Inc.  
Address Box 486, Ellinwood, Kansas 67526 License No. 462  
Operation Completed: Hour 11:40 A Day 6 Month 6 Year 1977

The above well was plugged as follows:

Total Depth 4416' 8 5/8 csg set 420' cwc 325 sk.  
4 1/2 csg set 4406' cw 125 sk.  
Filled 4 1/2 csg W/sd (4416'-4375') dumped 3 sk cmt W/dump bailer. (4375'-4345')  
Cutoff & recovered 3018' of 4 1/2 csg.  
Allied Cementing Co. mixed & pumped down 8 5/8 csg with 15 sk gel & water W/100 lbs  
hulls, <sup>PTA 9</sup> followed with 80 sk 50-50 poz 2% -displaced with 8 sk gel & water & capped  
with 20 sk 50-50 poz 2% & shutin. FPP 500 lbs.

I hereby certify that the above well was plugged as herein stated.

Signed: L. M. Massery  
Well Plugging Supervisor

INVOICED  
DATE 6-7-77  
INV. NO. 5277-W