

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
JUN 29 1970
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Pickrell Drilling Company

Complete Address 705 4th Nat'l Bank Bldg., Wichita, Kansas

Lease Name Wittman "C" Well No. 1

Location SW SW NE Sec. 18 Twp. 20 Rge. (E) (W) 21

County Ness Total Depth 4440

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Russ Casing Pulling, Inc.

Address Box License No.

Operation Completed: Hour 2:30P Day 25 Month 6 Year 1970

The above well was plugged as follows:

Total Depth 4440' 8 5/8 csg set at 269' cwc 160 sk.

5 1/2 csg set at 4435' cw 100 sk cmt.

5 1/2 csg PBTD 4413' with top perf. (4372)

Filled 5 1/2 csg W/sd (4350-4413) Dumped 5 sk cmt W/dump bailer. (4310-4350)

Cutoff and recovered 3009' of 5 1/2 csg.

Pumped thru 8 5/8 plug container with 12 sk gel W/3 sk hulls, - 50 sk poz 6% - 8 sk gel - plug and 50 sk poz 6%.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 6/30/70

INV. NO. 2133-W

Signed: Ben F. Massey
Well Plugging Supervisor