

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

RECEIVED
STATE CORPORATION COMMISSION
JAN 13 1976
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Mack Oil Co.
Complete Address 812 Union Center, Wichita, Kansas
Lease Name Wittman Well No. 1
Location 150' SE of C SW NW Sec. 18 Twp. 20 Rge. (E) (W) 21
County Ness Total Depth 4357'
Abandoned Oil Well Gas Well Input Well SWD Well D & A XX
Other well as hereafter indicated
Plugging Contractor Thomas Drlg.
Address Wichita, Kansas License No.
Operation Completed: Hour 3:45 P Day 9 Month 1 Year 1976

The above well was plugged as follows:

RTD 4357' 8 5/8 csg set 300' cwc 200 sk. Plg. Mat. 50-50 poz 2% total gel.
Gunned pits, circulated heavy mud, set 50 sk cmt plug at 550' thru drill pipe.
Heavy mud to 240' set 25 sk cmt plug thru drill pipe. Heavy mud to 40' set solid
bridge & 10 sk cmt plug to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo Massey
Well Plugging Supervisor

DATE 1-14-76

INV. NO. 2560-W