

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
OCT 22 1968
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Brandt - Clark

Complete Address: 737 First Nat'l Bank Bldg., Wichita, Kansas

Lease Name Kramer Well No. 21

Location C SE NW Sec. 10 Twp. 20 Rge. 21 (E) (W) XX

County Ness Total Depth 4462

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated:

Plugging Contractor: Leben Drlg.

Address: Wichita, Kansas License No.

Operation Completed: Hour 11A Day 17 Month 10 Year 1968

The Above well was plugged as follows:

RTD 4462' 8 5/8 csg set at 532' cwc

Gunned pits, circulated heavy mud, set cementing plug at 720' and displaced 50 sc cmt
thru drill pipe. Heavy mud to 480' set cementing plug and displaced 25 sc cement thru
drill pipe. Heavy mud to 40' set cementing plug, 1/2 sc hulls and 10 sc cement to base
of cellar. Plugged rat hole with 2 sc cement.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: R. J. Murray
Well Plugging Supervisor

DATE 10/22/68
INV. NO. 8675-W